

Appendix F

Stormwater management

Appendix F Stormwater Management

As referred to in Section 6.4, no detailed flood modelling has been undertaken; however it is likely that the site will experience flooding in a Q100 flood event due to the proximity of the site to the creek.

Table F.1 Stormwater management

Collection, treatment and reuse component	Safety system	Stormwater management
Gravity collection system	<ul style="list-style-type: none"> Designed to relevant standards 	<ul style="list-style-type: none"> Single sewer line collecting wastewater from construction site office As the system will be closed and small, stormwater ingress may be considered negligible
Rising main	<ul style="list-style-type: none"> Designed to relevant standards 	<ul style="list-style-type: none"> Single rising main discharging wastewater from the construction camp to the WWTP As the system will be closed and small, there will be no stormwater ingress may be considered negligible
Construction camp pumping station	<ul style="list-style-type: none"> High-level Alarm Water tight fibreglass reinforced plastic wet well with sealed lid External monitoring system Duty and standby pumps to be provided 	<ul style="list-style-type: none"> Wet well will be covered to minimise stormwater ingress into the system 4 kL of storage provided
Package WWTP and pumping station	<ul style="list-style-type: none"> High-level alarms Series of poly plastic tanks with sealed lids External monitoring system Duty and standby pumps to be provided within pumping station 	<ul style="list-style-type: none"> Above ground tanks will be sealed to a minimum of 1 m above ground level Tanks will be located on a hard stand The risk of stormwater ingress and subsequent overtopping is considered minimal as tanks will be raised and sealed 3 kL of storage provided within pump station wet well
Effluent storage pond	<ul style="list-style-type: none"> Pond will be fully lined with a HDPE liner or similar Freeboard of 500 mm 	<ul style="list-style-type: none"> Pond liner will minimise the risk of groundwater contamination Freeboard will reduce the risk of overtopping It is proposed to use the treated effluent for dust suppression and irrigation to (where possible) provide an effective full 5 days of storage during wet weather Any overflows will be released in a controlled process to minimise erosion and sediment impact

Collection, treatment and reuse component	Safety system	Stormwater management
Effluent irrigation area	<ul style="list-style-type: none"> A drain should be used to collect effluent if the irrigation application rates result in surface flow along the full length of the irrigation furrow. 	<ul style="list-style-type: none"> To minimise the risk of runoff it is proposed to incorporate a "dry period" of 12 hours after the last rainfall (event > 10 mm) prior to applying any effluent. This is intended to allow the surface soil to drain to the point where a further effluent can be applied without causing runoff. Effluent should not be applied under conditions that will result in runoff or ponding of effluent. Routine monitoring of soil and water quality will be required. A monitoring schedule has been outlined in the CEMP.