

# Table of contents

- E. Executive summary
  - E1. Introduction..... E-1
    - E1.1 Project proponents..... E-1
    - E1.2 Project rationale ..... E-2
    - E1.3 Relationships to other projects..... E-4
    - E1.4 Project alternatives ..... E-4
    - E1.5 Regulatory framework and environmental impact assessment process ..... E-6
    - E1.6 Consultation..... E-14
  - E2. Project description..... E-16
  - E3. Environmental values, potential impacts and mitigation..... E-27
    - E3.1 Climate, natural hazards and climate change..... E-27
    - E3.2 Land..... E-27
    - E3.3 Flora..... E-29
    - E3.4 Aquatic ecology..... E-31
    - E3.5 Terrestrial fauna..... E-35
    - E3.6 Surface water resources ..... E-36
    - E3.7 Groundwater resources ..... E-41
    - E3.8 Water quality..... E-43
    - E3.9 Air quality ..... E-44
    - E3.10 Greenhouse gas emissions..... E-44
    - E3.11 Noise and vibration..... E-44
    - E3.12 Waste..... E-44
    - E3.13 Transport ..... E-45
    - E3.14 Cultural heritage ..... E-46
    - E3.15 Social impact..... E-47
    - E3.16 Economics ..... E-48
    - E3.17 Hazard and risk ..... E-48
    - E3.18 Cumulative impacts ..... E-49
    - E3.19 Offsets ..... E-50
  - E4. Environmental management ..... E-50
  - E5. Conclusion and recommendations ..... E-50
- 1. Introduction
  - 1.1 Overview ..... 1-1
  - 1.2 Project proponent..... 1-1
    - 1.2.1 GAWB ..... 1-1
    - 1.2.2 SunWater..... 1-2

1.2.3	Environmental record.....	1-3
1.3	Project description.....	1-3
1.4	Project rationale.....	1-5
1.4.1	Strategic and economic justification.....	1-5
1.4.2	Technical feasibility and commercial drivers.....	1-7
1.5	Relationships to other projects .....	1-10
1.5.1	Existing Eden Bann Weir .....	1-10
1.5.2	Fitzroy Barrage.....	1-10
1.5.3	Gladstone-Fitzroy pipeline project .....	1-10
1.6	Project alternatives.....	1-12
1.6.1	Fitzroy Barrage.....	1-12
1.6.2	GAWB second water source options.....	1-12
1.6.3	Water storage infrastructure.....	1-13
1.6.4	Non-infrastructure options.....	1-14
1.6.5	No development option.....	1-14
1.7	Environmental impact assessment process.....	1-14
1.7.1	Methodology of the EIS .....	1-14
1.7.2	Objectives of the draft EIS.....	1-17
1.7.3	Submissions .....	1-17
1.8	Public consultation .....	1-19
1.8.1	Consultation methodology.....	1-19
1.8.2	Stakeholder identification and involvement .....	1-19
1.8.3	Integration of consultation program into Project EIS .....	1-21
2.	Project description	
2.1	Overview of the Project.....	2-1
2.2	Project location.....	2-4
2.2.1	Eden Bann Weir Project footprint .....	2-4
2.2.2	Rookwood Weir Project footprint .....	2-10
2.2.3	Downstream areas.....	2-16
2.3	Design of water resources infrastructure.....	2-16
2.3.1	Water storage infrastructure.....	2-16
2.3.1.1	Basis of design.....	2-16
2.3.1.2	Development of preliminary construction methodologies and cost estimates .....	2-17
2.3.1.3	Eden Bann Weir design .....	2-18
2.3.1.4	Rookwood Weir design.....	2-26
2.3.1.5	Aquatic fauna passage .....	2-31
2.3.2	Water distribution infrastructure .....	2-32
2.3.3	Other Project specific infrastructure and services.....	2-32
2.3.3.1	Access roads .....	2-32

2.3.3.2	River crossings.....	2-34
2.3.3.3	Gauging stations and monitoring weirs.....	2-35
2.3.3.4	Site facilities.....	2-35
2.3.3.5	Power supply infrastructure .....	2-36
2.3.3.6	Telecommunications infrastructure .....	2-36
2.3.3.7	Resource extraction areas.....	2-36
2.4	Construction phase .....	2-39
2.4.1	Overview .....	2-39
2.4.1.1	Construction areas.....	2-39
2.4.1.2	Workforce and accommodation.....	2-45
2.4.2	Pre-construction activities .....	2-45
2.4.3	Construction .....	2-46
2.4.3.1	General activities .....	2-46
2.4.3.2	Construction inputs, handling and storage .....	2-47
2.4.3.3	Hazardous materials .....	2-49
2.4.3.4	Water supply.....	2-49
2.4.3.5	Restoration of temporary construction areas .....	2-50
2.4.4	Construction methodology and work sequence.....	2-50
2.4.4.1	Weirs .....	2-50
2.4.4.2	Diversion strategies.....	2-61
2.4.4.3	River crossings.....	2-62
2.4.5	Commissioning.....	2-63
2.5	Operation phase .....	2-63
2.5.1	Overview .....	2-63
2.5.2	Drawdown strategy and flow releases.....	2-63
2.5.3	Flap gate operation strategy.....	2-65
2.5.4	Fishway operation.....	2-66
2.5.5	Control systems .....	2-66
2.5.6	Maintenance.....	2-66
2.6	Decommissioning and rehabilitation .....	2-67
3.	Legislation and project approvals .....	
3.1	Overview .....	3-1
3.2	Commonwealth legislation and approvals .....	3-1
3.2.1	Aboriginal and Torres Strait Islander Heritage Protection Act 1984.....	3-1
3.2.2	Environment Protection and Biodiversity Conservation Act 1999.....	3-1
3.2.2.1	EPBC Act Environmental Offset Policy.....	3-2
3.2.2.2	International conventions and treaties .....	3-2
3.2.3	Great Barrier Reef Marine Park Act 1975 .....	3-3
3.2.4	National Environment Protection Council Act 1994.....	3-3

3.2.5	Native Title Act 1993.....	3-3
3.2.6	National Water Quality Management Strategy.....	3-4
3.3	Queensland legislation.....	3-5
3.3.1	Aboriginal Cultural Heritage Act 2003.....	3-5
3.3.2	Disaster Management Act 2003.....	3-5
3.3.3	Environmental Offsets Act 2014.....	3-5
3.3.4	Environmental Protection Act 1994.....	3-7
3.3.4.1	Greentape reduction.....	3-8
3.3.4.2	Environmental protection policies.....	3-9
3.3.5	Fire and Emergency Services Act 1990.....	3-9
3.3.6	Fisheries Act 1994.....	3-10
3.3.7	Forestry Act 1959.....	3-10
3.3.8	Health Act 1937.....	3-11
3.3.9	Land Protection (Pest and Stock Route Management) Act 2002.....	3-11
3.3.10	Land Act 1994.....	3-12
3.3.11	Local Government Act 2009.....	3-12
3.3.12	Marine Parks Act 2004.....	3-12
3.3.13	Nature Conservation Act 1992.....	3-12
3.3.13.1	Nature Conservation (Wildlife Management) Regulation 2006.....	3-13
3.3.14	Queensland Heritage Act 1992.....	3-13
3.3.15	Regional Planning Interests Act 2014.....	3-13
3.3.16	State Development and Public Works Organisation Act 1971.....	3-14
3.3.16.1	Statewide water program of works.....	3-14
3.3.16.2	Private infrastructure facility.....	3-15
3.3.17	Public Health Act 2005.....	3-15
3.3.18	Sustainable Planning Act 2009.....	3-15
3.3.18.1	State Assessment and Referral Agency.....	3-16
3.3.18.2	State Planning Policy.....	3-16
3.3.18.3	State development and assessment provisions.....	3-17
3.3.18.4	Resource entitlements.....	3-18
3.3.18.5	Community Infrastructure Designation.....	3-19
3.3.19	Tobacco and Other Smoking Products Act 1998.....	3-19
3.3.20	Transport Infrastructure Act 1994.....	3-19
3.3.21	Vegetation Management Act 1999.....	3-20
3.3.22	Waste Reduction and Recycling Act 2011.....	3-20
3.3.22.1	Waste Reduction and Recycling Regulation 2011.....	3-21
3.3.23	Water Act 2000.....	3-21
3.3.23.1	Water Resource (Fitzroy Basin) Plan 2011.....	3-21
3.3.23.2	Fitzroy Basin Resource Operations Plan.....	3-22

3.3.23.3	Permits and licences.....	3-22
3.3.24	Water Supply (Safety and Reliability) Act 2008 .....	3-23
3.3.25	Work Health and Safety Act 2011 .....	3-24
3.4	Regional plans and strategies .....	3-24
3.4.1	Central Queensland Regional Water Supply Strategy.....	3-24
3.4.2	Central Queensland Regional Plan.....	3-25
3.5	Local planning schemes.....	3-25
3.5.1	Overview .....	3-25
3.5.2	Fitzroy Shire Planning Scheme 2005.....	3-26
3.5.3	Livingstone Shire Planning Scheme 2005.....	3-27
3.5.4	Duaranga Shire Planning Scheme 2007.....	3-27
3.5.5	Woorabinda Aboriginal Shire Council Planning Scheme 2014.....	3-28
3.6	Local laws.....	3-28
3.6.1	Rockhampton Regional Council and Livingstone Shire Council.....	3-28
3.6.1.1	Local Law No. 1 (Administration) 2011 .....	3-28
3.6.1.2	Local Law No. 3 (Community and Environmental Management) 2011 .....	3-28
3.6.2	Central Highlands Regional Council.....	3-29
3.6.2.1	Local Law No. 1 (Administration) 2012.....	3-29
3.6.2.2	Local Law No. 3 (Community and Environmental Management) 2012 .....	3-29
3.6.3	Woorabinda Aboriginal Shire Council.....	3-30
3.6.3.1	Local Law No. 1 - (Administration) 2011 .....	3-30
3.6.3.2	Local Law No. 3 - (Community and Environmental Management) 2011 .....	3-30
3.6.3.3	Local Law No. 7 - (Indigenous Community Land Management) 2011 .....	3-31
3.6.3.4	By-Law No. 4 (Control of Nuisances) .....	3-31
3.7	Project approvals .....	3-31
4.	Climate, natural hazards and climate change .....	
4.1	Overview .....	4-1
4.2	Local climate and seasonal conditions.....	4-1
4.3	Extremes of climate and natural or induced hazards.....	4-4
4.3.1	Overview .....	4-4
4.3.2	Floods .....	4-4
4.3.3	Tropical cyclones.....	4-6
4.3.4	Severe storms.....	4-8
4.3.5	Drought.....	4-9
4.3.6	Extreme temperatures.....	4-9
4.4	Climate change.....	4-9
4.4.1	Overview .....	4-9
4.4.2	Approach and methodology.....	4-10
4.4.3	Projections .....	4-10

4.4.3.1	Rainfall, temperature and evaporation.....	4-10
4.4.3.2	Extreme climatic events .....	4-11
4.4.4	Potential impacts and adaptation strategies .....	4-11
4.5	Summary .....	4-13
5.	Land	
5.1	Overview .....	5-1
5.2	Scenic amenity and lighting .....	5-1
5.2.1	Introduction.....	5-1
5.2.1.1	Approach and methodology .....	5-1
5.2.2	Description of environmental values .....	5-2
5.2.2.1	Landscape character.....	5-2
5.2.2.2	View points .....	5-4
5.2.3	Potential impacts and mitigation measures .....	5-11
5.2.3.1	Visual project elements.....	5-11
5.2.3.2	Visual impact assessment.....	5-11
5.2.3.3	Lighting impacts and mitigation measures.....	5-14
5.2.4	Summary.....	5-14
5.3	Topography, geology and soils.....	5-15
5.3.1	Introduction.....	5-15
5.3.1.1	Approach and methodology .....	5-15
5.3.2	Description of environmental values .....	5-16
5.3.2.1	Topography .....	5-16
5.3.2.2	Geology .....	5-20
5.3.2.3	Land systems and soils.....	5-26
5.3.3	Potential impacts and mitigation measures .....	5-37
5.3.3.1	Topography .....	5-37
5.3.3.2	Geology .....	5-37
5.3.3.3	Land systems and soils.....	5-40
5.3.4	Summary.....	5-42
5.4	Contaminated land.....	5-43
5.4.1	Introduction.....	5-43
5.4.1.1	Approach and methodology .....	5-43
5.4.1.2	Regulatory framework.....	5-45
5.4.2	Description of environmental values .....	5-45
5.4.2.1	Overview .....	5-45
5.4.2.2	Eden Bann Weir .....	5-46
5.4.2.3	Rookwood Weir.....	5-48
5.4.3	Potential impacts and mitigation measures .....	5-51
5.4.3.1	Overview .....	5-51

5.4.3.2	Management of possible contamination sites .....	5-51
5.4.3.3	Spill or leak prevention and management .....	5-52
5.4.4	Summary.....	5-52
5.5	Land use and tenure.....	5-53
5.5.1	Introduction.....	5-53
5.5.1.1	Approach and methodology.....	5-53
5.5.2	Description of environmental values .....	5-54
5.5.2.1	Land tenure .....	5-54
5.5.2.2	Land use .....	5-54
5.5.2.3	Reserves, protected and sensitive environmental areas.....	5-61
5.5.2.4	Mining and petroleum tenure .....	5-61
5.5.2.5	Key resource areas .....	5-71
5.5.2.6	Existing and proposed infrastructure.....	5-72
5.5.2.7	Stock routes.....	5-74
5.5.2.8	Native title.....	5-74
5.5.2.9	Residential and recreational use areas.....	5-74
5.5.3	Potential impacts and mitigation measures .....	5-76
5.5.3.1	Land tenure .....	5-76
5.5.3.2	Land use .....	5-92
5.5.3.3	Reserves, protected and sensitive environmental areas.....	5-93
5.5.3.4	Mining and petroleum tenure .....	5-93
5.5.3.5	Key resource areas .....	5-93
5.5.3.6	Existing and future infrastructure.....	5-94
5.5.3.7	Stock routes.....	5-94
5.5.3.8	Native title.....	5-94
5.5.3.9	Residential and recreational and industrial use.....	5-96
5.5.4	Summary.....	5-96
6.	Flora	
6.1	Introduction.....	6-1
6.1.1	Overview .....	6-1
6.1.2	Approach and methodology.....	6-1
6.1.2.1	Desktop assessment.....	6-1
6.1.2.2	Nangura vegetation assessment methodology.....	6-1
6.1.2.3	Regional ecosystem calculations.....	6-5
6.1.2.4	Likelihood of occurrence determination .....	6-5
6.1.3	Regulatory framework .....	6-6
6.2	Existing environment .....	6-6
6.2.1	Sensitive environmental areas .....	6-6
6.2.2	Threatened ecological communities.....	6-6

6.2.3	Regional ecosystems .....	6-8
6.2.3.1	Regional ecosystems within the Project footprint.....	6-8
6.2.3.2	Regional ecosystems in the surrounding landscape .....	6-20
6.2.3.3	Bio-condition analysis.....	6-20
6.2.4	High value regrowth.....	6-21
6.2.5	Essential habitat.....	6-21
6.2.6	Biodiversity and connectivity.....	6-24
6.2.7	Conservation significant flora species .....	6-24
6.2.8	Culturally significant flora.....	6-24
6.2.9	Flora of commercial significance.....	6-24
6.2.10	Horticultural crops .....	6-39
6.2.11	Weeds and other non-native plants.....	6-39
6.3	Potential impacts and mitigation measures.....	6-40
6.3.1	Overview.....	6-40
6.3.2	Loss of vegetation.....	6-41
6.3.2.1	Loss of threatened ecological communities .....	6-41
6.3.2.2	Loss of remnant vegetation .....	6-42
6.3.2.3	Loss of high value regrowth.....	6-44
6.3.2.4	Loss of essential habitat.....	6-45
6.3.2.5	Loss of conservation significant flora species .....	6-47
6.3.3	Habitat fragmentation and loss of connectivity.....	6-48
6.3.4	Introduction of weed and non-native plants.....	6-48
6.3.5	Mitigation measures.....	6-48
6.4	Summary.....	6-50
7.	Aquatic ecology	
7.1	Introduction.....	7-1
7.1.1	Overview.....	7-1
7.1.2	Approach and methodology.....	7-1
7.1.2.1	Desktop assessment.....	7-1
7.1.2.2	Aquatic habitat calculation.....	7-2
7.1.2.3	Field surveys.....	7-2
7.1.2.4	Ecological risk assessment.....	7-8
7.1.2.5	Design process.....	7-9
7.1.3	Regulatory framework .....	7-16
7.2	Existing environment .....	7-17
7.2.1	Aquatic habitat .....	7-17
7.2.1.1	Aquatic habitats within the project footprints.....	7-17
7.2.1.2	Upstream aquatic habitat .....	7-28
7.2.1.3	Downstream aquatic habitat .....	7-28



7.2.1.4	Habitat dynamics .....	7-34
7.2.1.5	Habitat disturbance and sensitivity.....	7-36
7.2.2	Aquatic species.....	7-36
7.2.2.1	Overview .....	7-36
7.2.2.2	Fish.....	7-38
7.2.2.3	Reptiles.....	7-51
7.2.2.4	Mammals.....	7-56
7.2.2.5	Macroinvertebrates .....	7-58
7.2.2.6	Macrophytes and algae.....	7-59
7.2.2.7	Marine fauna species .....	7-61
7.3	Potential impacts and mitigation measures.....	7-62
7.3.1	Overview .....	7-62
7.3.2	Loss of aquatic habitat.....	7-63
7.3.2.1	Potential impacts .....	7-63
7.3.2.2	Mitigation measures .....	7-63
7.3.3	Alteration of aquatic habitats .....	7-64
7.3.3.1	Overview .....	7-64
7.3.3.2	Potential impacts to freshwater turtles .....	7-65
7.3.3.3	Potential impacts to estuarine crocodiles .....	7-67
7.3.3.4	Potential impacts to fish.....	7-67
7.3.3.5	Potential impacts to macroinvertebrates .....	7-68
7.3.3.6	Mitigation measures .....	7-69
7.3.4	Inundation of turtle nesting habitat.....	7-69
7.3.4.1	Potential impact.....	7-69
7.3.4.2	Mitigation measures .....	7-71
7.3.5	Habitat degradation associated with construction activities .....	7-71
7.3.5.1	Potential impacts .....	7-71
7.3.5.2	Mitigation measures .....	7-72
7.3.6	Habitat degradation associated with changes to water quality during operations.....	7-73
7.3.6.1	Overview .....	7-73
7.3.6.2	Potential impacts to freshwater turtles .....	7-74
7.3.6.3	Potential impacts to estuarine crocodiles .....	7-74
7.3.6.4	Potential impacts to fish.....	7-74
7.3.6.5	Potential impacts to macroinvertebrates .....	7-75
7.3.6.6	Mitigation measures .....	7-75
7.3.7	Changes in downstream flow regime during operations .....	7-76
7.3.7.1	Potential impact.....	7-76
7.3.7.2	Mitigation measures .....	7-78
7.3.8	Fauna injury and mortality.....	7-78

7.3.8.1	Potential impacts .....	7-78
7.3.8.2	Mitigation measures .....	7-79
7.3.9	Restriction of movement .....	7-81
7.3.9.1	Overview .....	7-81
7.3.9.2	Potential impacts to freshwater turtles .....	7-82
7.3.9.3	Potential impacts to estuarine crocodiles .....	7-83
7.3.9.4	Potential impacts to fish .....	7-83
7.3.9.5	Potential impacts to macroinvertebrates .....	7-84
7.3.9.6	Mitigation measures .....	7-84
7.3.10	Increased pest and weed species .....	7-87
7.3.10.1	Potential impact .....	7-87
7.3.10.2	Mitigation measures .....	7-88
7.3.11	Impacts to downstream estuarine/marine habitat and species .....	7-88
7.3.12	Impacts on conservation significant aquatic fauna .....	7-88
7.3.12.1	Fitzroy River turtle .....	7-88
7.3.12.2	Estuarine crocodile .....	7-90
7.4	Summary .....	7-90
8.	Terrestrial fauna	
8.1	Introduction .....	8-1
8.1.1	Overview .....	8-1
8.1.2	Approach and methodology .....	8-1
8.1.2.1	Desktop assessment .....	8-1
8.1.2.2	Field surveys .....	8-2
8.1.2.3	Likelihood of occurrence assessment .....	8-7
8.1.2.4	Habitat assessment .....	8-8
8.1.3	Regulatory framework .....	8-9
8.2	Existing environment .....	8-9
8.2.1	Habitat .....	8-9
8.2.1.1	Eden Bann Weir .....	8-9
8.2.1.2	Rookwood Weir .....	8-20
8.2.2	Fauna species .....	8-32
8.2.2.1	Overview .....	8-32
8.2.2.2	Birds .....	8-33
8.2.2.3	Mammals .....	8-41
8.2.2.4	Reptiles .....	8-47
8.2.2.5	Amphibians .....	8-51
8.2.2.6	Back on Track Biodiversity Action Plan species .....	8-52
8.2.2.7	Introduced species .....	8-53
8.3	Potential impacts and mitigation measures .....	8-54

8.3.1	Overview .....	8-54
8.3.2	Individual fauna injury and mortality .....	8-55
8.3.2.1	Potential impacts .....	8-55
8.3.2.2	Mitigation measures .....	8-55
8.3.3	Disruption to behaviour of localised wildlife assemblages .....	8-56
8.3.3.1	Potential impacts .....	8-56
8.3.3.2	Mitigation measures .....	8-57
8.3.4	Loss of terrestrial habitat due to clearing .....	8-57
8.3.4.1	Potential impacts .....	8-57
8.3.4.2	Mitigation measures .....	8-59
8.3.5	Loss of terrestrial habitat due to impoundment .....	8-59
8.3.5.1	Overview .....	8-59
8.3.5.2	Potential impacts on birds .....	8-61
8.3.5.3	Potential impacts on mammals .....	8-63
8.3.5.4	Potential impacts on reptiles .....	8-65
8.3.5.5	Mitigation measures .....	8-65
8.3.6	Fragmentation of riparian habitat .....	8-65
8.3.6.1	Potential impacts .....	8-65
8.3.6.2	Mitigation measures .....	8-67
8.3.7	Degradation of habitat .....	8-67
8.3.7.1	Potential impacts .....	8-67
8.3.7.2	Mitigation measures .....	8-68
8.3.8	Encroachment of feral animal species .....	8-69
8.3.8.1	Potential impacts .....	8-69
8.3.8.2	Mitigation measures .....	8-69
8.3.9	Impacts on conservation significant terrestrial fauna .....	8-69
8.3.9.1	Overview .....	8-69
8.3.9.2	Koala .....	8-70
8.3.9.3	Powerful owl .....	8-72
8.3.9.4	Squatter pigeon .....	8-73
8.4	Summary .....	8-76
9.	Surface water resources	
9.1	Introduction .....	9-1
9.1.1	Overview .....	9-1
9.1.2	Regulatory framework .....	9-1
9.1.2.1	Overview .....	9-1
9.1.2.2	Water Resource (Fitzroy Basin) Plan 2011 .....	9-2
9.1.2.3	Fitzroy Basin Resource Operations Plan .....	9-5
9.1.3	Approach and methodology .....	9-9

9.1.3.1	Overview .....	9-9
9.1.3.2	Yield modelling.....	9-9
9.1.3.3	Stream flow hydrology .....	9-12
9.1.3.4	Flood hydrology.....	9-14
9.1.3.5	Hydraulic modelling.....	9-14
9.2	Existing environment .....	9-15
9.2.1	Catchment characteristics.....	9-15
9.2.1.1	The Fitzroy basin.....	9-15
9.2.1.2	The Fitzroy subcatchment .....	9-17
9.2.1.3	The Dawson subcatchment .....	9-21
9.2.1.4	The Mackenzie subcatchment.....	9-21
9.2.2	Stream flow hydrology.....	9-23
9.2.3	Flooding.....	9-24
9.2.4	Fluvial processes and morphology .....	9-25
9.2.5	Water users and future reservations .....	9-27
9.2.5.1	Supplemented water supplies .....	9-27
9.2.5.2	Unsupplemented water supplies.....	9-29
9.2.5.3	Unallocated water .....	9-30
9.2.6	Water resource infrastructure and operational regimes .....	9-31
9.3	Potential impacts and mitigation measures.....	9-32
9.3.1	Construction .....	9-32
9.3.1.1	Overview .....	9-32
9.3.1.2	Disruption and diversion of flows – weir infrastructure.....	9-32
9.3.1.3	Disruption and diversion of flows – associated infrastructure.....	9-34
9.3.1.4	Drawdown .....	9-34
9.3.2	Operation.....	9-34
9.3.2.1	Overview .....	9-34
9.3.2.2	Inundation and operational strategy .....	9-35
9.3.2.3	Altered stream flow patterns .....	9-38
9.3.2.4	Water allocation security objectives .....	9-40
9.3.2.5	Environmental flow objectives .....	9-42
9.3.2.6	Altered flood flow regimes .....	9-45
9.3.2.7	Changes to river morphology (fluvial processes).....	9-57
9.3.2.8	Uncontrolled releases of water due to system failure.....	9-59
9.4	Summary.....	9-60
9.4.1	Regulatory framework .....	9-60
9.4.2	Approach and methodology.....	9-60
9.4.3	Existing environment.....	9-61
9.4.4	Potential impacts and mitigation measures .....	9-62

9.4.4.1	Construction.....	9-62
9.4.4.2	Operations.....	9-62
10.	Groundwater resources	
10.1	Introduction.....	10-1
10.1.1	Overview .....	10-1
10.1.2	Regulatory framework.....	10-1
10.1.3	Approach and methodology .....	10-1
10.2	Existing environment .....	10-2
10.2.1	Geology and hydrogeology .....	10-2
10.2.1.1	Alluvial aquifers.....	10-3
10.2.1.2	Tertiary sediment aquifers .....	10-3
10.2.1.3	Gogango overfold aquifers.....	10-3
10.2.1.4	Groundwater levels, flow and water quality .....	10-4
10.2.2	Groundwater resource allocation.....	10-6
10.2.3	Groundwater dependent ecosystems .....	10-11
10.3	Potential impacts and mitigation measures.....	10-12
10.3.1	Construction.....	10-12
10.3.2	Operations .....	10-15
10.3.2.1	Upstream impacts .....	10-15
10.3.2.2	Downstream impacts .....	10-17
10.4	Summary.....	10-18
11.	Water quality	
11.1	Introduction.....	11-1
11.1.1	Overview .....	11-1
11.1.2	Regulatory framework.....	11-1
11.1.2.1	Overview.....	11-1
11.1.2.2	National Environment Protection Measures .....	11-2
11.1.2.3	National Water Quality Management Strategy.....	11-2
11.1.2.4	Water Quality Guidelines for the Great Barrier Reef Marine Park .....	11-2
11.1.2.5	Water Act 2000.....	11-3
11.1.2.6	Environmental Protection Act 1994.....	11-3
11.1.2.7	Queensland water quality guidelines .....	11-8
11.1.3	Assessment scope and objective.....	11-8
11.1.4	Approach and methodology .....	11-9
11.1.4.1	Overview.....	11-9
11.1.4.2	Desktop assessment.....	11-9
11.1.4.3	Data analysis.....	11-12
11.1.4.4	Water quality objectives and guideline values .....	11-14
11.2	Existing environment .....	11-15

11.2.1	Catchment and sub-catchment characteristics.....	11-15
11.2.2	Seasonal variation.....	11-18
11.2.2.1	The Fitzroy Basin .....	11-18
11.2.2.2	Receiving environment.....	11-18
11.2.3	Fitzroy River.....	11-19
11.2.3.1	Fitzroy River at The Gap.....	11-19
11.2.3.2	Fitzroy River at Riverslea.....	11-28
11.2.4	Lower Dawson River.....	11-33
11.2.5	Lower Mackenzie River.....	11-37
11.2.6	Fitzroy River estuary and Great Barrier Reef World Heritage Area receiving waters..	11-41
11.2.6.1	Overview.....	11-41
11.2.6.2	Sedimentation.....	11-42
11.2.6.3	Nutrient loads .....	11-44
11.2.6.4	Pesticides and herbicides .....	11-44
11.2.7	Contaminated land.....	11-45
11.2.8	Groundwater .....	11-45
11.3	Potential impacts and mitigation measures.....	11-46
11.3.1	Construction phase .....	11-46
11.3.2	Operations phase.....	11-47
11.3.2.1	Initial filling phase.....	11-47
11.3.2.2	Normal operations phase.....	11-52
11.3.2.3	Downstream erosion.....	11-54
11.3.2.4	Water quality impacts on the GBRWHA .....	11-54
11.4	Summary.....	11-55
12.	Air quality	
12.1	Introduction.....	12-1
12.1.1	Overview .....	12-1
12.1.2	Approach and methodology .....	12-1
12.1.3	Regulatory framework.....	12-1
12.1.3.1	Commonwealth.....	12-1
12.1.3.2	State .....	12-2
12.2	Description of environmental values.....	12-3
12.2.1	Overview .....	12-3
12.2.2	Sensitive receptors.....	12-3
12.2.3	Meteorological influences .....	12-6
12.2.4	Existing regional pollution sources .....	12-6
12.2.5	Existing local pollution sources.....	12-7
12.2.6	Typical baseline levels .....	12-7
12.3	Potential impacts and mitigation measures.....	12-8

12.3.1	Overview .....	12-8
12.3.2	Construction phase impacts and mitigation measures.....	12-8
12.3.2.1	Dust generation and human health risk.....	12-8
12.3.2.2	Impacts to flora and fauna .....	12-9
12.3.2.3	Mitigation and management measures .....	12-10
12.3.3	Operational phase impacts and mitigation measures .....	12-11
12.4	Summary.....	12-11
13.	Greenhouse gas emissions	
13.1	Introduction.....	13-1
13.1.1	Overview .....	13-1
13.1.2	Regulatory framework.....	13-1
13.1.3	Approach and methodology .....	13-2
13.1.3.1	Assessment scope .....	13-2
13.1.3.2	Assessment methodology.....	13-3
13.1.3.3	Qualifications.....	13-3
13.2	Description of environmental values.....	13-6
13.3	Potential impacts and mitigation measures.....	13-6
13.3.1	Predicted greenhouse gas emissions .....	13-6
13.3.2	Mitigation measures .....	13-8
13.4	Summary.....	13-8
14.	Noise and vibration	
14.1	Introduction.....	14-1
14.1.1	Overview .....	14-1
14.1.2	Approach and methodology .....	14-1
14.1.3	Regulatory framework.....	14-2
14.1.3.1	Overview.....	14-2
14.1.3.2	Environmental Protection Act 1994.....	14-2
14.1.3.3	Planning for noise control guideline.....	14-3
14.1.3.4	Assessment of low frequency noise guideline .....	14-4
14.1.3.5	Noise and vibration from blasting guideline.....	14-4
14.1.3.6	Construction vibration .....	14-5
14.2	Existing environment .....	14-5
14.2.1	Noise and vibration sensitive receptors.....	14-5
14.2.2	Typical background noise and vibration levels .....	14-8
14.3	Potential impacts and mitigation measures.....	14-9
14.3.1	Construction phase impacts and mitigation measures.....	14-9
14.3.1.1	Predicted construction noise .....	14-9
14.3.1.2	Impacts at sensitive receptors .....	14-11
14.3.1.3	Impacts to native fauna .....	14-12

14.3.1.4	Impacts to livestock .....	14-12
14.3.1.5	Night-time works .....	14-12
14.3.1.6	Vibration impacts.....	14-13
14.3.1.7	Blasting impacts.....	14-13
14.3.1.8	Mitigation and management measures .....	14-14
14.3.2	Operational phase impacts .....	14-15
14.4	Summary .....	14-15
15.	Waste	
15.1	Introduction.....	15-1
15.1.1	Overview .....	15-1
15.1.2	Methodology .....	15-1
15.1.3	Relevant legislation, policies and strategies.....	15-1
15.2	Project waste streams and associated impacts .....	15-3
15.2.1	Overview .....	15-3
15.2.2	Construction related waste streams .....	15-3
15.2.3	Operation related waste streams .....	15-3
15.2.4	Decommissioning related waste streams .....	15-3
15.3	Waste management .....	15-6
15.3.1	Waste Management Plan .....	15-6
15.3.2	Waste management measures.....	15-6
15.3.3	Waste disposal.....	15-8
15.4	Summary .....	15-9
16.	Transport	
16.1	Introduction.....	16-1
16.1.1	Overview .....	16-1
16.1.2	Assessment scope and objectives .....	16-1
16.1.3	Approach and methodology .....	16-2
16.1.4	Qualifications.....	16-4
16.2	Existing environment .....	16-5
16.2.1	Rail network.....	16-5
16.2.2	Port facilities.....	16-5
16.2.3	Airport facilities .....	16-7
16.2.4	Road network.....	16-7
16.2.5	School, public passenger and active transport infrastructure and services.....	16-22
16.3	Potential impacts and mitigation measures.....	16-22
16.3.1	Overview .....	16-22
16.3.2	Rail network.....	16-24
16.3.3	Road network and flooding.....	16-24
16.3.4	Weir access and construction.....	16-26



16.3.4.1	Basis of weir construction traffic assessment .....	16-26
16.3.4.2	Weir construction traffic generation .....	16-29
16.3.4.3	Weir construction road and traffic impact assessment .....	16-31
16.3.5	Road and crossing construction.....	16-38
16.3.6	School transport infrastructure and services .....	16-40
16.3.7	Operational traffic.....	16-40
16.4	Summary .....	16-40
17.	Cultural heritage	
17.1	Overview .....	17-1
17.2	Indigenous cultural heritage.....	17-1
17.2.1	Introduction.....	17-1
17.2.1.1	Approach and methodology .....	17-1
17.2.1.2	Regulatory framework .....	17-2
17.2.1.3	Aboriginal parties .....	17-3
17.2.2	Description of existing Indigenous cultural heritage values.....	17-5
17.2.3	Potential impacts and mitigation measures.....	17-6
17.2.4	Summary .....	17-11
17.3	Non-Indigenous cultural heritage.....	17-12
17.3.1	Introduction.....	17-12
17.3.1.1	Approach and methodology .....	17-12
17.3.1.2	Regulatory framework .....	17-13
17.3.2	Description of existing non-Indigenous cultural heritage .....	17-14
17.3.3	Potential impacts and mitigation measures.....	17-16
17.3.3.1	Great Barrier Reef World Heritage Area.....	17-16
17.3.3.2	Riverslea hut .....	17-17
17.3.4	Summary .....	17-17
18.	Social impact assessment	
18.1	Introduction.....	18-1
18.1.1	Overview .....	18-1
18.1.2	Approach and methodology .....	18-1
18.1.3	Study area .....	18-3
18.2	Social baseline .....	18-7
18.2.1	Local study area demographics.....	18-7
18.2.1.1	Eden Bann Weir and Rookwood Weir Project footprints.....	18-7
18.2.1.2	Gogango.....	18-8
18.2.2	Regional study area demographics .....	18-8
18.2.2.1	Population.....	18-8
18.2.2.2	Age, gender and family composition.....	18-9
18.2.2.3	Indigenous population.....	18-10

18.2.2.4	Industry, occupation, labour force and unemployment.....	18-10
18.2.2.5	Temporary accommodation.....	18-11
18.2.3	Social infrastructure, services and facilities .....	18-11
18.2.3.1	Utilities.....	18-11
18.2.3.2	Communications .....	18-12
18.2.3.3	Transport infrastructure.....	18-12
18.2.3.4	Health and emergency services.....	18-13
18.3	Potential impacts and mitigation measures.....	18-14
18.3.1	Overview .....	18-14
18.3.2	Planning phase.....	18-14
18.3.2.1	Potential impacts.....	18-14
18.3.2.2	Mitigation and management measures .....	18-15
18.3.3	Construction phase .....	18-16
18.3.3.1	Potential impacts.....	18-16
18.3.3.2	Mitigation and management measures .....	18-19
18.3.4	Operational phase.....	18-20
18.3.4.1	Potential impacts.....	18-20
18.3.4.2	Mitigation and management measures .....	18-23
18.3.5	Monitoring potential social impacts.....	18-25
18.3.6	Summary of social impacts and mitigation measures .....	18-25
19.	Economics	
19.1	Introduction.....	19-1
19.1.1	Overview .....	19-1
19.1.2	Approach and Methodology .....	19-1
19.1.3	Study area .....	19-3
19.1.4	Description of the base case.....	19-5
19.1.5	Description of development scenarios .....	19-5
19.2	Existing local and regional economies.....	19-6
19.2.1	Gross regional product.....	19-6
19.2.2	Population.....	19-6
19.2.3	Labour force and income.....	19-7
19.2.4	Key industries and economic contribution .....	19-7
19.2.5	Key regional markets and factor prices .....	19-9
19.2.5.1	Labour market .....	19-9
19.2.5.2	Housing, residential land and rental markets.....	19-9
19.2.5.3	Agricultural land value.....	19-10
19.2.5.4	Construction services and building inputs market .....	19-10
19.2.6	Regional competitive advantage and expected future growth.....	19-10
19.3	Project benefits.....	19-10

19.3.1	Increased ability to satisfy water demand.....	19-10
19.3.2	Avoided costs.....	19-10
19.3.3	Residual value of infrastructure at Year 25.....	19-11
19.3.4	Regional economic benefits.....	19-11
19.3.5	Ecological and social impacts.....	19-11
19.4	Benefit Cost Analysis results.....	19-12
19.4.1	Summary of economic impacts.....	19-14
19.5	Sustainable development .....	19-14
20.	Hazard and risk	
20.1	Introduction.....	20-1
20.1.1	Overview .....	20-1
20.1.2	Methodology .....	20-1
20.1.2.1	Hazard and risk assessment methodology .....	20-1
20.1.2.2	Other relevant assessments.....	20-4
20.1.3	Regulatory framework.....	20-4
20.2	Existing environment .....	20-5
20.2.1	Human health and safety.....	20-5
20.2.2	Emergency services .....	20-6
20.2.3	Land use.....	20-6
20.2.4	Environmentally sensitive receptors.....	20-6
20.2.5	Natural or induced hazards.....	20-7
20.2.5.1	Climate related hazards.....	20-7
20.2.5.2	Bushfires.....	20-7
20.2.5.3	Seismic activity .....	20-7
20.2.5.4	Landslides.....	20-10
20.2.6	Wildlife hazards .....	20-10
20.2.7	Unexploded ordinance.....	20-10
20.3	Construction phase hazards and risks .....	20-10
20.3.1	Overview .....	20-10
20.3.2	Risks to human health and safety .....	20-20
20.3.3	Roads and traffic hazards.....	20-20
20.3.4	Environmentally hazardous substances .....	20-21
20.3.5	Natural or induced hazards.....	20-24
20.3.5.1	Flooding.....	20-24
20.3.5.2	Tropical cyclones and severe storms.....	20-25
20.3.5.3	Extreme temperatures.....	20-25
20.3.5.4	Bushfires.....	20-25
20.3.5.5	Seismic activity .....	20-25
20.3.5.6	Landslides.....	20-25

20.3.5.7	Climate change.....	20-26
20.3.6	Wildlife hazards .....	20-26
20.4	Operational phase hazard and risk.....	20-26
20.4.1	Overview .....	20-26
20.4.2	Risks to human health and safety .....	20-33
20.4.3	Roads and traffic hazards.....	20-33
20.4.4	Natural or induced hazards.....	20-33
20.4.4.1	Flooding.....	20-33
20.4.4.2	Tropical cyclones and severe storms.....	20-34
20.4.4.3	Extreme temperatures.....	20-34
20.4.4.4	Bushfires.....	20-34
20.4.4.5	Seismic activity .....	20-34
20.4.4.6	Landslides.....	20-34
20.4.4.7	Climate change.....	20-35
20.4.5	Wildlife hazards .....	20-35
20.4.6	Weir failure.....	20-35
20.4.6.1	Overview.....	20-35
20.4.6.2	Failure impact assessment .....	20-36
20.4.6.3	Failure mode analysis .....	20-36
20.4.6.4	Gate fault tree analysis.....	20-37
20.4.6.5	Electrical and control system.....	20-37
20.5	Decommissioning.....	20-38
20.6	Cumulative risk.....	20-38
20.7	Risk management.....	20-38
20.7.1	Safety in Design.....	20-38
20.7.2	Spill response plan.....	20-39
20.7.3	Fire/explosion emergency response plan.....	20-39
20.7.4	Traffic management and traffic incident response.....	20-40
20.7.5	Emergency response.....	20-40
20.7.5.1	Emergency response equipment.....	20-41
20.7.5.2	External emergency services.....	20-41
20.8	Summary.....	20-41
21.	Cumulative impacts	
21.1	Introduction.....	21-1
21.1.1	Overview .....	21-1
21.1.2	Background.....	21-1
21.1.3	Objective .....	21-1
21.1.4	Methodology .....	21-1
21.2	Existing pressures.....	21-9

21.2.1	Catchment pressures.....	21-9
21.2.2	Regional pressure.....	21-12
21.2.3	Bio-subregion pressures.....	21-12
21.2.4	Local pressures .....	21-13
21.3	Cumulative Project impacts.....	21-13
21.4	Proposed developments.....	21-15
21.5	Project’s contribution to potential cumulative impacts.....	21-20
21.6	Summary.....	21-29
22.	Offsets	
22.1	Introduction.....	22-1
22.1.1	Overview .....	22-1
22.1.2	Regulatory framework.....	22-1
22.1.2.1	Overview.....	22-1
22.1.2.2	Environmental Offsets Act 2014.....	22-1
22.1.2.3	Environmental Offsets Regulation 2014 .....	22-2
22.1.2.4	Queensland Environmental Offsets Policy.....	22-3
22.1.3	Approach and methodology .....	22-4
22.2	Project offset requirements .....	22-5
22.2.1	Overview .....	22-5
22.2.2	Prescribed activities.....	22-5
22.2.3	Prescribed environmental matters.....	22-5
22.2.3.1	Regulated vegetation.....	22-5
22.2.3.2	Connectivity areas.....	22-6
22.2.3.3	Wetlands and watercourses.....	22-7
22.2.3.4	Protected wildlife habitat.....	22-7
22.2.3.5	Waterway providing for fish passage.....	22-9
22.3	Offset proposal – Fitzroy River turtle .....	22-9
22.3.1	Overview .....	22-9
22.3.2	Nesting habitat.....	22-10
22.3.2.1	Impact calculator.....	22-10
22.3.2.2	Offset calculator.....	22-10
22.3.2.3	Offset management plan .....	22-12
22.3.2.4	Offset staging .....	22-14
22.3.3	Aquatic habitat.....	22-15
22.3.3.1	Impact calculation.....	22-15
22.3.3.2	Financial offset proposal.....	22-16
22.3.3.3	Offset staging .....	22-16
22.4	Summary.....	22-16
23.	Environmental management plan	

23.1	Introduction.....	23-1
23.1.1	Overview .....	23-1
23.1.2	Project overview .....	23-1
23.1.3	Environmental management plan and structure .....	23-3
23.2	Environmental management framework.....	23-4
23.2.1	Environment and sustainability policy .....	23-4
23.2.1.1	Gladstone Area Water Board.....	23-4
23.2.1.2	SunWater.....	23-4
23.2.2	Responsibilities, authority and commitment.....	23-5
23.2.2.1	Responsibilities – construction.....	23-5
23.2.2.2	Responsibility – operation.....	23-6
23.2.3	Legal obligations and compliance.....	23-7
23.2.4	Training, competence and induction.....	23-11
23.2.4.1	Overview.....	23-11
23.2.4.2	Awareness inductions .....	23-11
23.2.4.3	Tool box talks .....	23-11
23.2.4.4	Training needs assessment .....	23-12
23.2.5	Communication.....	23-12
23.2.6	Documentation, document control and records .....	23-13
23.2.7	Project management integration.....	23-13
23.2.8	Emergency preparedness and response.....	23-13
23.2.9	Incident management .....	23-14
23.2.9.1	Construction phase.....	23-14
23.2.9.2	Operation phase.....	23-15
23.2.10	Community consultation and complaints procedure .....	23-15
23.2.11	Environmental reporting.....	23-16
23.2.11.1	Internal .....	23-16
23.2.11.2	External.....	23-17
23.2.12	Environmental auditing.....	23-17
23.2.13	Review and continuous improvement .....	23-17
23.3	Environmental aspects and their impacts .....	23-18
23.4	Construction management plans .....	23-20
23.4.1	Soil Management Programme.....	23-21
23.4.2	Contaminated Land Management Programme.....	23-23
23.4.3	Nature Conservation Management Programme .....	23-23
23.4.4	Water Management Programme.....	23-28
23.4.5	Air Management Programme .....	23-30
23.4.6	Greenhouse Gas Emissions Management Programme.....	23-31
23.4.7	Noise and Vibration Management Programme.....	23-32

23.4.8	Waste Management Programme.....	23-35
23.4.9	Road use and Traffic Management Programme.....	23-37
23.4.10	Cultural Heritage Management Programme.....	23-38
23.4.11	Community Management Programme.....	23-39
23.4.12	Hazardous Material Management Programme.....	23-40
23.4.13	Emergency Management Programme.....	23-42
23.5	Operation management plans.....	23-43
23.5.1	Nature Conservation Management Programme.....	23-43
23.5.2	Water Management Programme.....	23-46
23.5.3	Community Management Programme.....	23-48
23.5.4	Emergency Management Programme.....	23-49
24.	Conclusion and recommendations	
24.1	Overview.....	24-1
24.2	Conclusions and recommendations.....	24-1
25.	References	
25.1	Introduction.....	25-1
25.2	Project description.....	25-1
25.3	Legislation and project approvals.....	25-1
25.4	Climate, natural hazards and climate change.....	25-2
25.5	Land.....	25-4
25.5.1	Scenic amenity and lighting.....	25-4
25.5.2	Topography, geology and soils.....	25-4
25.5.3	Contaminated land.....	25-5
25.5.4	Land use and tenure.....	25-6
25.6	Flora.....	25-6
25.7	Aquatic ecology.....	25-7
25.8	Terrestrial fauna.....	25-11
25.9	Surface water resources.....	25-13
25.10	Groundwater resources.....	25-15
25.11	Water quality.....	25-15
25.12	Air quality.....	25-18
25.13	Greenhouse gas emissions.....	25-18
25.14	Noise and vibration.....	25-19
25.15	Waste.....	25-19
25.16	Transport.....	25-20
25.17	Cultural heritage.....	25-20
25.17.1	Indigenous cultural heritage.....	25-20
25.17.2	Non-Indigenous cultural heritage.....	25-20
25.18	Social.....	25-21

25.19	Economic.....	25-22
25.20	Hazard and risk.....	25-23
25.21	Cumulative impacts.....	25-23
25.22	Offsets.....	25-24
25.23	Environmental management plan.....	25-25
25.24	Conclusions and recommendations.....	25-25



## Table index

Table E-1	Draft EIS structure.....	E-7
Table E-2	Approvals summary.....	E-9
Table E-3	Project stakeholders.....	E-14
Table E-4	Consultation phases.....	E-15
Table E-5	Eden Bann Weir existing and proposed development levels.....	E-21
Table E-6	Rookwood Weir proposed development levels.....	E-24
Table E-7	Remnant vegetation within the Project footprint and surrounding region.....	E-30
Table E-8	Brigalow TEC impacts.....	E-31
Table E-9	Theoretical Project yields.....	E-39
Table 1-1	Draft EIS structure.....	1-16
Table 1-2	Project stakeholders.....	1-20
Table 1-3	EIS consultation stages and timeframes.....	1-22
Table 2-1	Eden Bann Weir existing and proposed development levels.....	2-19
Table 2-2	Rookwood Weir proposed development levels.....	2-26
Table 2-3	River crossing access.....	2-34
Table 2-4	Provisional quantities of construction materials.....	2-39
Table 2-5	Project construction areas.....	2-40
Table 2-6	Construction activities.....	2-46
Table 2-7	Eden Bann Weir construction methodology and work sequence.....	2-51
Table 2-8	Rookwood construction methodology and work sequence.....	2-52
Table 2-9	Cofferdam levels and associated flood flows – Eden Bann Weir.....	2-61
Table 2-10	Gate operation opening sequence.....	2-65
Table 3-1	Project prescribed activities.....	3-6
Table 3-2	Applicable SDAP codes.....	3-18
Table 3-3	Level of assessment – Fitzroy Shire.....	3-26
Table 3-4	Level of assessment – Livingstone Shire.....	3-27
Table 3-5	Level of assessment – Duinga Shire.....	3-27
Table 3-6	Level of assessment – WASC.....	3-28
Table 3-7	Approvals summary.....	3-33
Table 3-8	Approval pathway options.....	3-38
Table 4-1	Temperature summary.....	4-3

Table 4-2	Evaporation summary.....	4-4
Table 4-3	Climate change projections summary for Central Queensland.....	4-11
Table 4-4	Potential impacts associated with climate change for water infrastructure projects across Australia.....	4-12
Table 4-5	Climate change impact and adaption summary.....	4-13
Table 5-1	Assessment of potential landscape impacts .....	5-2
Table 5-2	Assessment of visual sensitivity.....	5-1
Table 5-3	Significance of the impact.....	5-2
Table 5-4	Eden Bann Weir and impoundment existing visual environment .....	5-7
Table 5-5	Rookwood Weir site and inundation zone existing visual environment .....	5-9
Table 5-6	Eden Bann Weir visual impact assessment.....	5-12
Table 5-7	Rookwood Weir visual impact assessment.....	5-13
Table 5-8	Summary of impacts.....	5-15
Table 5-9	Land systems and soils within a 5 km buffer along the length of the Fitzroy River .....	5-28
Table 5-10	Soil characteristics of Project area construction footprints.....	5-32
Table 5-11	Eden Bann Weir subject lots and potential contamination sites.....	5-48
Table 5-12	Rookwood subject lots and potential contamination sites.....	5-49
Table 5-13	Eden Bann Weir subject lots and tenure status .....	5-79
Table 5-14	Rookwood subject lots and tenure status .....	5-87
Table 5-15	Reserves and protected areas directly impacted by the Project .....	5-93
Table 6-1	Likelihood of occurrence determination.....	6-5
Table 6-2	Threatened ecological communities predicted to occur in the Project area .....	6-7
Table 6-3	Regional ecosystems within the Project footprints .....	6-8
Table 6-4	Extent of relevant regional ecosystems within the region.....	6-20
Table 6-5	Conservation significant flora potentially relevant to the Project footprint.....	6-35
Table 6-6	Significant weeds identified during field surveys.....	6-39
Table 6-7	Affected Brigalow TEC.....	6-41
Table 6-8	Remnant vegetation within the Project footprint (ha).....	6-43
Table 6-9	Impacted regional ecosystems by VM Act class .....	6-44
Table 6-10	High value regrowth impacted by the Project.....	6-45
Table 6-11	Mapped essential habitat affected by the Eden Bann Weir impoundment.....	6-46
Table 6-12	Mapped essential habitat affected by the Rookwood Weir impoundment.....	6-47

Table 6-13	Remnant vegetation within the Project footprint and surrounding region.....	6-51
Table 7-1	Summary of survey effort .....	7-4
Table 7-2	Fishway design specifications and success criteria.....	7-11
Table 7-3	Current level of impoundment in rivers relative to the Project .....	7-17
Table 7-4	Aquatic habitat types – Eden Bann Weir.....	7-18
Table 7-5	Aquatic habitat types – Rookwood Weir Project footprint .....	7-24
Table 7-6	Aquatic habitat seasonal dynamics .....	7-35
Table 7-7	Summary of aquatic fauna species predicted to occur or recorded during field surveys.....	7-37
Table 7-8	Fish species previously recorded within the study area .....	7-39
Table 7-9	Catch composition from seasonal field surveys.....	7-40
Table 7-10	Seasonal flow range covered by the provision of fishlocks.....	7-87
Table 8-1	Survey effort, techniques and locations – Eden Bann Weir .....	8-5
Table 8-2	Survey effort, techniques and locations – Rookwood Weir.....	8-6
Table 8-3	Summary of nest survey effort.....	8-7
Table 8-4	Likelihood of occurrence determination.....	8-8
Table 8-5	Terrestrial habitat types, characteristics and values – Eden Bann Weir.....	8-11
Table 8-6	Terrestrial habitat types, characteristics and values – Rookwood Weir.....	8-22
Table 8-7	Eden Bann Weir fauna species predicted to occur or recorded as occurring.....	8-32
Table 8-8	Rookwood Weir fauna species predicted to occur or recorded as occurring.....	8-33
Table 8-9	Conservation significant birds – likelihood of occurrence assessment.....	8-36
Table 8-10	Conservation significant mammals – likelihood of occurrence assessment.....	8-42
Table 8-11	Conservation significant reptiles – likelihood of occurrence assessment .....	8-48
Table 8-12	Introduced terrestrial fauna species.....	8-53
Table 8-13	Habitat types lost to clearing for construction.....	8-58
Table 8-14	Habitat types lost to impoundment .....	8-60
Table 8-15	Koala habitat within the Project footprint .....	8-70
Table 8-16	Significance of impact on the koala.....	8-71
Table 8-17	Significance of impact on the powerful owl .....	8-72
Table 8-18	Significance of impact on the squatter pigeon (southern).....	8-75
Table 9-1	Unsupplemented water allocation security objectives .....	9-2
Table 9-2	Seasonal base flow objectives.....	9-4

Table 9-3	Medium to high flow objectives.....	9-4
Table 9-4	First post-winter flow event objectives .....	9-5
Table 9-5	Project development scenarios.....	9-11
Table 9-6	IQQM-Project compliance reporting criteria.....	9-11
Table 9-7	Flow analysis data locations .....	9-12
Table 9-8	Supplemented water allocations .....	9-28
Table 9-9	Fitzroy Water Management Area water allocation groups .....	9-30
Table 9-10	Eden Bann Weir construction cofferdam levels and associated flood flows.....	9-33
Table 9-11	Compliance with high and medium priority supplemented water user group WASOs .....	9-40
Table 9-12	Compliance with unsupplemented water user group WASOs .....	9-41
Table 9-13	Compliance with seasonal base flow environmental objectives.....	9-42
Table 9-14	Compliance with medium to high flow environmental objectives.....	9-43
Table 9-15	Compliance with first post-winter flow event objectives.....	9-44
Table 9-16	Links between the Water Resource (Fitzroy Basin) Plan 2011 and Fitzroy Basin Resource Operations Plan 2014 and the Project .....	9-63
Table 10-1	Groundwater chemistry zones within the Project area.....	10-5
Table 10-2	Registered bores within proximity to the Project footprint.....	10-8
Table 11-1	Summary of water quality datasets .....	11-12
Table 11-2	Summary of DNRM water quality data from the Fitzroy River at The Gap.....	11-20
Table 11-3	Summary of SunWater water quality data for Eden Bann Weir .....	11-22
Table 11-4	Median values and water quality objectives for The Gap/Eden Bann Weir.....	11-23
Table 11-5	Blue green algae guideline hazard levels .....	11-28
Table 11-6	Summary of water quality data from the Fitzroy River at Riverslea.....	11-29
Table 11-7	Median values and water quality objectives at Riverslea.....	11-32
Table 11-8	Summary of water quality data from the Dawson River at Beckers.....	11-34
Table 11-9	Median values and water quality objectives for aquatic ecosystems at Beckers.....	11-36
Table 11-10	Summary of water quality data from the Mackenzie River at Coolmaringa.....	11-38
Table 11-11	Median values and water quality objectives for aquatic ecosystems at Coolmaringa.....	11-40
Table 11-12	Groundwater chemistry zones within the Project area.....	11-45
Table 11-13	Rates of decay for total nitrogen and total phosphorous .....	11-48
Table 12-1	Project air quality objectives.....	12-2

Table 12-2	Air quality sensitive receptors.....	12-6
Table 12-3	Typical baseline levels .....	12-8
Table 13-1	Greenhouse gas assessment assumptions .....	13-4
Table 13-2	Annual greenhouse gas emissions.....	13-6
Table 13-3	Construction phase greenhouse gas inventory.....	13-7
Table 14-1	Acoustic quality objectives for dwellings.....	14-3
Table 14-2	Recommended outdoor background noise planning levels.....	14-4
Table 14-3	Guidance on effects of vibration levels for human comfort (BS 5228.2 – 2009) .....	14-5
Table 14-4	Noise and vibration sensitive receptors.....	14-8
Table 14-5	Estimated background noise levels .....	14-9
Table 14-6	Predicted construction plant noise levels.....	14-10
Table 14-7	Predicted construction noise over distance.....	14-11
Table 14-8	Predicted construction noise at nearest sensitive receptors .....	14-11
Table 14-9	Predicted construction plant vibration levels .....	14-13
Table 15-1	Construction waste streams.....	15-4
Table 15-2	Waste management measures.....	15-7
Table 16-1	Existing roads in the Project area.....	16-12
Table 16-2	Hydraulic immunity of current and proposed crossing infrastructure .....	16-25
Table 16-3	Construction staging and activities .....	16-27
Table 16-4	Construction equipment and vehicle types .....	16-28
Table 16-5	Traffic generation for cement and fly ash delivery .....	16-29
Table 16-6	Construction traffic generation for Eden Bann Weir.....	16-32
Table 16-7	Construction traffic generation for Rookwood Weir .....	16-33
Table 16-8	Road use management plan commitments.....	16-42
Table 17-1	Significance assessment of sites and structures of potential cultural heritage value ..	17-16
Table 18-1	Estimated resident population in the regional study area (2006-2011) .....	18-8
Table 18-2	Population projections for the regional study area (2011-2031).....	18-9
Table 18-3	Unemployment and labour force status in the regional study area.....	18-10
Table 18-4	Emergency services in proximity to the Project .....	18-14
Table 18-5	Flood impact on land holdings pre and post-development.....	18-22
Table 18-6	Relevant management plans and strategies applicable to managing social impacts..	18-23
Table 18-7	Summary of social impacts and mitigation measures .....	18-26

Table 19-1	Schedule for costs and benefits.....	19-2
Table 19-2	Development scenarios evaluated.....	19-5
Table 19-3	Nominal gross regional product.....	19-6
Table 19-4	Estimated resident population in the regional study area (2006-2011).....	19-7
Table 19-5	Unemployment and labour force status within the regional study area.....	19-7
Table 19-6	Median rental and house prices.....	19-9
Table 19-7	Benefit Cost Analysis results.....	19-12
Table 19-8	Sensitivity analysis results for estimated theoretical high priority yields.....	19-13
Table 19-9	Sensitivity analysis results for capped yield (76,000 ML/a).....	19-13
Table 19-10	Comparative analysis of the NSED core objectives.....	19-15
Table 20-1	Risk and significance matrix.....	20-2
Table 20-2	Likelihood of occurrence.....	20-2
Table 20-3	Consequence of occurrence.....	20-3
Table 20-4	Human sensitive receptors.....	20-5
Table 20-5	Earthquakes resulting in MMI 3 and above.....	20-8
Table 20-6	Construction phase hazard and risk assessment.....	20-11
Table 20-7	Indicative list of environmentally hazardous substances.....	20-22
Table 20-8	Likely quantities, storage and transport of environmentally hazardous substances ...	20-22
Table 20-9	Operation phase hazard and risk assessment.....	20-27
Table 20-10	Fault tree analysis results for crest gate operation.....	20-37
Table 21-1	Current level of impoundment of main rivers relative to the Project.....	21-10
Table 21-2	Extent of regional ecosystems within the bio-subregion study area.....	21-12
Table 21-3	The Project's potential cumulative impacts on environmental values.....	21-14
Table 21-4	Proposed projects.....	21-16
Table 21-5	Project's contribution to cumulative impacts.....	21-21
Table 22-1	Fitzroy River turtle nests offset management plan.....	22-13
Table 22-2	Aquatic habitat impact area and offset area.....	22-15
Table 23-1	Summary of Project EMP development approvals.....	23-8
Table 23-2	Project construction activities and impacts.....	23-18
Table 23-3	Project operation activities and potential impacts.....	23-19
Table 24-1	Theoretical Project yields.....	24-2

## Figure index

Figure E-1	EIS consultation activities and communication tools.....	E-14
Figure E-2	Project location.....	E-18
Figure E-3	Eden Bann Weir construction area.....	E-19
Figure E-4	Rookwood Weir construction area.....	E-20
Figure 1-1	Project location.....	1-4
Figure 1-2	EIS consultation activities and communication tools.....	1-20
Figure 2-1	Existing Eden Bann Weir views.....	2-5
Figure 2-2	Eden Bann Weir infrastructure and impoundment locations.....	2-6
Figure 2-3	Eden Bann Weir construction area.....	2-8
Figure 2-4	Eden Bann Weir access.....	2-9
Figure 2-5	Rookwood Weir site views.....	2-11
Figure 2-6	Rookwood Weir infrastructure and impoundment location.....	2-12
Figure 2-7	Rookwood Weir construction area.....	2-13
Figure 2-8	Rookwood Weir access.....	2-15
Figure 2-9	Flap gate (example).....	2-22
Figure 2-10	Eden Bann Weir Stage 2 ogee spillway section.....	2-23
Figure 2-11	Eden Bann Weir Stage 3 ogee (high level) spillway section with flap gates.....	2-23
Figure 2-12	Eden Bann Weir spillway longitudinal section including founding levels.....	2-24
Figure 2-13	Eden Bann Weir right bank outlets and fish lock design.....	2-25
Figure 2-14	Section through Eden Bann Weir environmental flow outlets.....	2-25
Figure 2-15	Rookwood Weir Stage 1 ogee spillway section.....	2-28
Figure 2-16	Rookwood Weir Stage 2 ogee spillway section.....	2-28
Figure 2-17	Rookwood Weir spillway longitudinal section including founding levels.....	2-29
Figure 2-18	Rookwood Weir right bank proposed outlets and fish lock design.....	2-30
Figure 2-19	Section through Rookwood Weir environmental flow outlets.....	2-30
Figure 2-20	Typical fish lock arrangement.....	2-31
Figure 2-21	Eden Bann Weir potential construction material resource areas.....	2-37
Figure 2-22	Rookwood Weir potential construction material resource areas.....	2-38
Figure 2-23	Glenroy Crossing layout.....	2-41
Figure 2-24	Riverslea Crossing layout.....	2-42
Figure 2-25	Foleyvale Crossing layout.....	2-43

Figure 2-26 Hanrahan Crossing layout .....2-44

Figure 2-27 Typical mobile concrete batching plant .....2-48

Figure 2-28 Typical mobile continuous concrete mixing plant .....2-49

Figure 2-29 Eden Bann Weir construction sequencing .....2-53

Figure 2-30 Rookwood Weir construction sequencing.....2-57

Figure 4-1 Climate statistics..... 4-2

Figure 4-2 Average annual rainfall (Rockhampton) ..... 4-3

Figure 4-3 Annual wind rose 09:00 am (left) and 03:00 pm (right) ..... 4-4

Figure 4-4 Significant flood peaks – Fitzroy River, Rockhampton..... 4-5

Figure 4-5 Average annual number of tropical cyclones (1969/70 – 2005/06)..... 4-7

Figure 4-6 Recorded tropical cyclones within 100 km of Rockhampton (1906-2006) ..... 4-8

Figure 5-1 Eden Bann Weir landscape character..... 5-3

Figure 5-2 Rookwood Weir site landscape character..... 5-4

Figure 5-3 Eden Bann Weir view point locations..... 5-5

Figure 5-4 Rookwood Weir view point locations ..... 5-6

Figure 5-5 Regional topographical features .....5-17

Figure 5-6 Eden Bann Weir Project area topographical features .....5-18

Figure 5-7 Rookwood Project area topographical features .....5-19

Figure 5-8 Regional geology.....5-22

Figure 5-9 Eden Bann Weir geological section.....5-24

Figure 5-10 Rookwood Weir site geological section.....5-25

Figure 5-11 Soil types – Eden Bann Weir.....5-30

Figure 5-12 Soil types – Rookwood.....5-31

Figure 5-13 Eden Bann Weir strategic cropping areas .....5-38

Figure 5-14 Rookwood Weir strategic cropping land.....5-39

Figure 5-15 Eden Bann Weir subject lots and potential contamination sites.....5-47

Figure 5-16 Rookwood subject lots and potential contamination sites.....5-50

Figure 5-17 Eden Bann Weir land tenure.....5-55

Figure 5-18 Rookwood land tenure .....5-56

Figure 5-19 Local government areas.....5-57

Figure 5-20 Eden Bann Weir land use.....5-59

Figure 5-21 Rookwood land use.....5-60



Figure 5-22 Reserves, protected areas and sensitive environmental areas .....5-62

Figure 5-23 Eden Bann Weir exploration permits for minerals .....5-63

Figure 5-24 Rookwood Weir exploration permits for minerals .....5-64

Figure 5-25 Eden Bann Weir exploration permits for petroleum and petroleum pipeline licences ...5-65

Figure 5-26 Rookwood exploration permits for petroleum and petroleum pipeline licences .....5-66

Figure 5-27 Eden Bann Weir exploration permits for coal .....5-67

Figure 5-28 Rookwood Weir exploration permits for coal.....5-68

Figure 5-29 Eden Bann Weir mineral development licences and mining leases.....5-69

Figure 5-30 Rookwood mineral development licences and mining leases.....5-70

Figure 5-31 Key resource areas, existing and proposed infrastructure.....5-73

Figure 5-32 Stock route network.....5-75

Figure 5-33 Extent of land interest and ownership illustrated.....5-77

Figure 5-34 Eden Bann Weir potentially affected properties.....5-78

Figure 5-35 Rookwood potentially affected properties.....5-86

Figure 6-1 Eden Bann Weir field survey sites..... 6-3

Figure 6-2 Rookwood Weir field survey sites ..... 6-4

Figure 6-3 Eden Bann Weir regional ecosystem mapping (index).....6-10

Figure 6-4 Rookwood Weir regional ecosystem mapping (index) .....6-15

Figure 6-5 Eden Bann Weir regrowth vegetation .....6-22

Figure 6-6 Rookwood Weir regrowth vegetation.....6-23

Figure 6-7 Eden Bann Weir Biodiversity Planning Assessment mapping.....6-25

Figure 6-8 Rookwood Weir Biodiversity Planning Assessment mapping.....6-30

Figure 7-1 Eden Bann Weir aquatic ecology survey sites..... 7-5

Figure 7-2 Rookwood Weir aquatic ecology fauna survey sites..... 7-6

Figure 7-3 Linear extent of in-channel aquatic habitats.....7-21

Figure 7-4 Spatial distribution of in-channel aquatic habitats and off-stream water bodies and creeks within the Eden Bann Weir Project footprint.....7-22

Figure 7-5 Spatial distribution of in-channel aquatic habitats and off-stream water bodies and creeks within the Rookwood Weir Project footprint .....7-27

Figure 7-6 Sensitive environmental areas.....7-30

Figure 7-7 Fitzroy Catchment fish stock locations.....7-42

Figure 7-8 Fish species encountered during seasonal field surveys.....7-44

Figure 7-9 Relationship between fish migration and flow in the Fitzroy Basin catchment.....7-45

Figure 7-10 Fitzroy Barrage fishway.....	7-47
Figure 7-11 Eden Bann Weir fish lock .....	7-49
Figure 7-12 Fitzroy River turtle.....	7-51
Figure 7-13 Fitzroy River turtle important habitat areas .....	7-52
Figure 7-14 Fitzroy River turtle nesting banks – Eden Bann Weir.....	7-53
Figure 7-15 Fitzroy River turtle nesting banks – Rookwood Weir project footprint.....	7-54
Figure 7-16 Fitzroy River turtle potential nesting bank habitat.....	7-55
Figure 7-17 Crocodile slide (Eden Bann Weir Project footprint) .....	7-56
Figure 7-18 Wildlife Online platypus record location.....	7-57
Figure 7-19 Macrophytes and algae.....	7-60
Figure 8-1 Eden Bann Weir terrestrial fauna survey sites.....	8-3
Figure 8-2 Rookwood Weir terrestrial fauna survey sites .....	8-4
Figure 8-3 Eden Bann Weir fauna habitat types .....	8-10
Figure 8-4 Eden Bann Weir Biodiversity Planning Assessment mapping.....	8-15
Figure 8-5 Rookwood Weir fauna habitat types .....	8-21
Figure 8-6 Rookwood Weir Biodiversity Planning Assessment mapping.....	8-27
Figure 8-7 Eden Bann Weir – location of threatened terrestrial fauna species .....	8-34
Figure 8-8 Rookwood Weir location of threatened terrestrial fauna species .....	8-35
Figure 8-9 Bird species within Project study areas.....	8-40
Figure 8-10 Mammal species within Project study areas .....	8-46
Figure 8-11 Lizard species within Project study areas.....	8-50
Figure 8-12 Snake species within the Project study areas .....	8-50
Figure 8-13 Frog species within the Project study areas.....	8-52
Figure 9-1 Fitzroy WRP plan area.....	9-3
Figure 9-2 Supplemented water supply schemes relative to the Project.....	9-6
Figure 9-3 Existing unsupplemented water management areas relative to the Project.....	9-7
Figure 9-4 Existing water allocation zones relative to the Project .....	9-8
Figure 9-5 Gauging stations and flow assessment locations within and near to Project areas.....	9-13
Figure 9-6 Existing and proposed water storage infrastructure in the Fitzroy Basin .....	9-16
Figure 9-7 Typical landscapes associated with the Fitzroy River .....	9-18
Figure 9-8 Eden Bann Weir surface water resources .....	9-19
Figure 9-9 Rookwood Weir surface water resources .....	9-20

Figure 9-10 Typical landscapes associated with the lower Dawson River .....9-22

Figure 9-11 Typical landscapes associated with the lower Mackenzie River .....9-22

Figure 9-12 Fitzroy River aerial overview .....9-26

Figure 9-13 Eden Bann Weir (Stage 2) operational storage volumes.....9-36

Figure 9-14 Rookwood Weir (Stage 1) operational storage volumes .....9-37

Figure 9-15 Estimated peak water levels for modelled AEPs pre- and post-development at Eden Bann Weir.....9-47

Figure 9-16 Overview of the 1 in 2 year AEP event pre- and post-development flood extents associated with Eden Bann Weir .....9-48

Figure 9-17 Overview of the 1 in 5 year AEP event pre- and post-development flood extents associated with Eden Bann Weir .....9-49

Figure 9-18 Overview of the 1 in 10 year AEP event pre- and post-development flood extents associated with Eden Bann Weir .....9-50

Figure 9-19 Estimated peak water levels for modelled AEPs pre- and post-development at Rookwood Weir .....9-52

Figure 9-20 Overview of the 1 in 2 year AEP event pre- and post-development flood extents associated with Rookwood Weir .....9-53

Figure 9-21 Overview of the 1 in 5 year AEP event pre- and post-development flood extents associated with Rookwood Weir .....9-54

Figure 9-22 Overview of the 1 in 10 year AEP event pre- and post-development flood extents associated with Rookwood Weir .....9-55

Figure 9-23 Critical velocity (cm/s) for erosion, transportation and deposition of sediment .....9-57

Figure 9-24 Sand deposition at Eden Bann Weir.....9-58

Figure 10-1 Fitzroy and Highlands groundwater management areas .....10-7

Figure 10-2 Eden Bann Weir - registered bores .....10-9

Figure 10-3 Rookwood Weir - registered bores.....10-10

Figure 10-4 Eden Bann Weir groundwater dependent ecosystems .....10-13

Figure 10-5 Rookwood Weir groundwater dependent ecosystems .....10-14

Figure 11-1 Fitzroy River Sub-basin plan area.....11-5

Figure 11-2 Dawson River Sub-basin plan area.....11-6

Figure 11-3 Mackenzie River Sub-basin plan area .....11-7

Figure 11-4 Data source locations .....11-11

Figure 11-5 Fitzroy Basin and sub-catchments .....11-16

Figure 11-6 Temperature within the Eden Bann Weir impoundment.....11-25

Figure 11-7 Dissolved oxygen concentration within the Eden Bann Weir impoundment.....11-26

Figure 11-8 Fitzroy region inshore water quality trends ..... 11-42

Figure 11-9 Project (Eden Bann Weir) TN and TP contribution to existing annual loads ..... 11-49

Figure 11-10 Project (Rookwood Weir) TN and TP contribution to existing annual loads ..... 11-50

Figure 11-11 Project (Eden Bann Weir and Rookwood Weir) TN and TP contribution to existing annual loads..... 11-51

Figure 12-1 Air quality sensitive receptors..... 12-4

Figure 14-1 Noise and vibration sensitive receptors..... 14-6

Figure 16-1 Traffic and transport assessment study area ..... 16-3

Figure 16-2 Port and airport locations..... 16-6

Figure 16-3 Road network and river crossings associated with Eden Bann Weir..... 16-8

Figure 16-4 Road network and river crossings associated with Rookwood Weir..... 16-9

Figure 16-5 A typical unsealed gravel local road in the study area ..... 16-11

Figure 16-6 A typical bitumen sealed local road in the study area ..... 16-11

Figure 16-7 Existing Bruce Highway / Atkinson Road intersection..... 16-17

Figure 16-8 Bruce Highway/Atkinson Road intersection predicted background traffic volumes .... 16-18

Figure 16-9 Glenroy Crossing..... 16-18

Figure 16-10 Existing Capricorn Highway / Third Street intersection at Gogango..... 16-19

Figure 16-11 Capricorn Highway/third Street intersection predicted background traffic volumes .... 16-20

Figure 16-12 Riverslea Crossing..... 16-20

Figure 16-13 Foleyvale Crossing..... 16-21

Figure 16-14 Hanrahan Crossing ..... 16-21

Figure 16-15 School bus routes ..... 16-23

Figure 16-16 Proposed transport routes for cement and fly ash..... 16-30

Figure 16-17 Bruce Highway/Atkinson Road intersection assessment summary ..... 16-34

Figure 16-18 Capricorn Highway/Third Street intersection assessment summary..... 16-36

Figure 17-1 Native title claim areas..... 17-4

Figure 17-2 Darumbal Endorsed Parties CHMP area..... 17-7

Figure 17-3 Gangulu Endorsed Parties CHMP area..... 17-8

Figure 17-4 Kangoulou and Ghungalu Endorsed Parties CHMP areas ..... 17-9

Figure 17-5 Jetimarala Endorsed Parties CHMP area..... 17-10

Figure 17-6 Sites and structures of potential non-Indigenous cultural heritage value..... 17-15

Figure 18-1 Eden Bann Weir local study area..... 18-4

Figure 18-2 Rookwood Weir local study area.....18-5

Figure 18-3 Regional study area.....18-6

Figure 19-1 Project location.....19-4

Figure 19-2 Employment by industry in the regional study area.....19-8

Figure 19-3 Composition of gross value added in the Fitzroy Region (\$m) .....19-8

Figure 20-1 Earthquakes recorded in Queensland from 1960 to 2013 .....20-9

Figure 21-1 Cumulative impact assessment.....21-2

Figure 21-2 Catchment study area.....21-4

Figure 21-3 Regional study area.....21-5

Figure 21-4 Bio-subregion study area.....21-6

Figure 21-5 Eden Bann Weir local study area.....21-7

Figure 21-6 Rookwood Weir local study area.....21-8

Figure 21-7 Land use in the Fitzroy Basin catchment.....21-9

Figure 21-8 Existing activities.....21-11

Figure 21-9 Proposed developments.....21-19

Figure 22-1 Fitzroy River turtle nesting habitat locations.....22-11