



Adani Mining Pty Ltd

NORTH GALILEE BASIN RAIL PROJECT

Environmental Impact Statement

Chapter 14 Transport

November 2013

Table of contents

14.	Transport	14-1
14.1	Purpose of chapter	14-1
14.2	Methodology	14-1
14.2.1	Study area	14-1
14.2.2	Data sources	14-2
14.2.3	Legislation and guidelines	14-2
14.2.4	Desktop assessment	14-2
14.2.5	Road performance assessment	14-3
14.2.6	Intersection analysis	14-4
14.2.7	Accident analysis	14-4
14.2.8	General assumptions	14-4
14.3	Existing environment	14-5
14.3.1	Road transport network	14-5
14.3.2	Rail transport network	14-15
14.3.3	Air transport facilities	14-19
14.3.4	Sea transport facilities	14-21
14.3.5	Proposed transport infrastructure	14-24
14.4	Development traffic generation	14-25
14.4.1	Construction	14-25
14.4.2	Operation	14-35
14.5	Potential impacts and mitigation measures	14-35
14.5.1	Construction	14-36
14.5.2	Operation	14-49
14.6	Summary of mitigation measures	14-49
14.7	Conclusion	14-52

Table index

Table 14-1	Data sources	14-2
Table 14-2	LOS for rural roads	14-3
Table 14-3	Maximum AADT for various LOS on rural roads on level terrain	14-4
Table 14-4	Key SCR and local roads	14-5
Table 14-5	Public road, stock route and road reserve crossings	14-6
Table 14-6	Occupational (private farm) trails	14-8
Table 14-7	Summary of key intersections	14-10
Table 14-8	Existing traffic volumes and LOS (2012)	14-12
Table 14-9	Percentage heavy vehicles on key roads	14-13
Table 14-10	QTRIP program of works (2013-14 to 2016-17)	14-24

Table 14-11 Estimated monthly material supply truck traffic generation – return trips	14-28
Table 14-12 Service vehicles indicative route	14-29
Table 14-13 FIFO vehicles indicative route	14-30
Table 14-14 Estimated DIDO traffic generation (return trips)	14-31
Table 14-15 Estimated monthly construction vehicles (return trips)	14-31
Table 14-16 Estimated monthly construction traffic on key roads within the study area (single trips)	14-33
Table 14-17 Annual operation workforce 2016 to 2026	14-35
Table 14-18 Impact of construction traffic on key roads – 2015	37
Table 14-19 Mitigation measures and timings related to construction and operation activities	14-50

Figure index

Figure 14-1 Key intersections	14-11
Figure 14-2 Heavy vehicle transport network	14-14
Figure 14-3 Freight rail transport network	14-17
Figure 14-4 Passenger rail transport network	14-18
Figure 14-5 Air transport facilities	14-20
Figure 14-6 Sea transport facilities	14-23
Figure 14-7 Bruce Highway/New Access Road treatment findings	14-40
Figure 14-8 Glenore Road/New Access Road treatment findings	14-41
Figure 14-9 Strathalbyn Road/New Access Road treatment findings	14-42
Figure 14-10 Bowen Developmental Road/New Access Road treatment findings	14-43
Figure 14-11 Bowen Developmental Road/New Access Road treatment findings	14-44
Figure 14-12 Suttor Developmental Road/Stratford Road treatment findings	14-45
Figure 14-13 Stratford Road/New Access Road treatment findings	14-46
Figure 14-14 Gregory Developmental Road/New Access Road treatment findings	14-47

14. Transport

14.1 Purpose of chapter

The purpose of this chapter is to assess the potential impacts of the NGBR Project on transport including existing transport infrastructure and performance. This chapter includes an overview of the existing environment, consideration of potential construction and operation impacts, and the identification of proposed mitigation and management measures. A detailed existing environment report for transport was prepared for the NGBR Project and is provided in Volume 2 Appendix K Transport. The key findings of that report are included within this chapter.

The transportation values that are considered in this chapter include:

- The road transport network including:
 - State-controlled and local road performance
 - Roads and stock routes intersected by the NGBR Project
 - Key intersection performance
 - Existing heavy vehicle network
 - Active transport network
- Rail transport network including:
 - Freight network
 - Passenger rail network
- Air transport facilities
- Sea transport facilities
- Proposed transport infrastructure.

This transport chapter was prepared in accordance with the Terms of Reference (TOR) for the NGBR Project. A table that cross-references the contents of this chapter and the TOR is included as Volume 2 Appendix A Terms of Reference cross-reference.

All mitigation and management measures identified in this chapter are included within Volume 2 Appendix P Environmental management plan framework.

14.2 Methodology

14.2.1 Study area

For the purpose of this report, the study area is defined by the NGBR Project preliminary investigation corridor (nominally 1,000 m wide) and the surrounding road network which will be utilised by construction and operation traffic to access the corridor, camp sites and ancillary infrastructure. The condition and capacity of existing rail, air and sea transport infrastructure that has the potential to be used by the NGBR Project, although outside of the study area, are also considered.

14.2.2 Data sources

The data sources relied upon for this transport assessment are summarised in Table 14-1.

Table 14-1 Data sources

Description	Source
Physical road network	Department of Natural Resources and Mines
Heavy vehicle network	Queensland Government - Higher mass limits map for vehicles with road friendly suspensions 2013
Railway facilities	Geosciences Australia
Air transport facilities	Geosciences Australia
Sea transport facilities	Geosciences Australia
Planned and future transport infrastructure	Queensland Transport and Roads Investment Program 2013-14 to 2016-17
Vehicular demand data	Department of Transport and Main Roads
Accident data	Department of Transport and Main Roads
Construction and operations traffic information	NGBR Project Concept Design Report (Aarvee Associates 2013)

14.2.3 Legislation and guidelines

This transport assessment has been conducted according to the Guidelines for the Assessment of Road Impacts of Developments (GARID), published by the Department of Transport and Main Roads (DTMR), 2006. GARID states that DTMR will not approve development unless any road impacts of the development can be managed to maintain a safe and efficient road system for all road users, as required by the *Transport Infrastructure Act 1994*. This approach is supported by the legislative powers of both the *Sustainable Planning Act 2009* and the *State Development and Public Works Organisation Act 1971* which enable DTMR to impose conditions to mitigate the road impacts of proposed developments as part of the development planning process. Other guidelines that were considered included:

- Austroads, "Guide to Traffic Engineering Practice - Part 2: Roadway Capacity"
- DTMR's Road Planning and Design Manual (RPDM), 2nd edition, 2013.
- Queensland Road Safety Action Plan 2013 – 2015.

The applicability of legislation to approvals for the NGBR Project is discussed in Volume 1 Chapter 20 Legislation and approvals.

14.2.4 Desktop assessment

A desktop assessment was undertaken and involved identification, and review of existing information relating to the extent, condition and capacity of the transportation values outlined in Section 14.1. This included:

- Identification and review of existing vehicular demand and percentage of heavy vehicles on the key roads and intersections

- Determination of the existing road link capacity for the impacted roads
- Identification and review of historical accident statistics in proximity to the key intersections
- Identification of any planned and future transport infrastructure upgrades which may impact the network performance in the study area.

The assessment conducted for this report has been desktop only and site investigations have not been conducted to verify desktop information.

14.2.5 Road performance assessment

A Level of Service (LOS) analysis on all approach roads (or road links) to the study intersections has been conducted with and without the potential NGBR Project traffic based on practical capacities determined from “Austroads Guide to Traffic Engineering Practice – Part 2: Roadway Capacity”. The Austroads guideline defines LOS as a qualitative measure for describing the operational performance of road. All the approach roads (or road links) to the study intersections can be classified as rural roads. The LOS performance criteria for rural roads are provided in Table 14-2.

Table 14-2 LOS for rural roads

LOS	Description	Performance
A	Free, unrestricted flow	Very good
B	Mostly free flow, few disruptions	Very good
C	Stable flow	Good
D	Mostly stable flow, some delays	Acceptable
E	Congested flow, delays common	Poor
F	Forced flow	Poor

Source: Austroads Guide to Traffic Engineering Practice Part 2: Roadway Capacity

For the LOS assessment of selected roads within the study area, the road terrain was assumed to be level and the design hour volume to Annual Average Daily Traffic (AADT) ratio was assumed to be 0.13 (13 per cent) for all selected road sections. A value of 0.13 (13 per cent) was selected as it falls within the middle of the Austroads Guide to Traffic Engineering Practice Part 2 recommended range of 11 per cent to 16 per cent for rural situations where peak to AADT percentages are not available.

AADT data for 2012 was sourced from DTMR. The AADT data available at the closest location to the study area was used. For any road section with multiple count sites, the highest AADT volume on the road was used for a conservative assessment.

Table 14-3 shows the values for various LOS categories on rural roads in level terrain, with varying ratios of design hour volume to AADT. For the purpose of the assessment, a practical capacity of 10,400 vehicles per day has been assumed as a threshold capacity limit (at LOS D) for rural roads. As per the Austroads guideline, LOS D is considered acceptable as it is an indication of generally stable flows with some delays. Remedial measures will be required for roads operating at LOS E or worse.

Table 14-3 Maximum AADT for various LOS on rural roads on level terrain

Design hour volume to AADT ratio	Level of service				
	A	B	C	D	E
0.10	2,400	4,800	7,900	13,500	22,900
0.11	2,200	4,400	7,200	12,200	20,800
0.12	2,000	4,000	6,600	11,200	19,000
0.13	1,900	3,700	6,100	10,400	17,600
0.14	1,700	3,400	5,700	9,600	16,300
0.15	1,600	3,200	5,300	9,000	15,200

Source: Austroads Guide to Traffic Engineering Practice, Part 2: Roadway Capacity, Table 3.9, from TRB Highway Capacity Manual (1985) Table 8.10

Therefore, the main performance criteria adopted for the assessment of approach roads (road links) within the study area was LOS D. For the assessment of percentage increase in AADT on the State-controlled roads (SCR), an increase of less than five per cent was considered acceptable.

The assessment has been conducted for eight key approach roads comprising four SCRs and four local council roads, which facilitate access for construction and operations traffic to and from the rail corridor, construction camp sites and ancillary infrastructure.

14.2.6 Intersection analysis

Detailed intersection modelling and assessment has not been undertaken due to the relatively low existing traffic volumes at key intersections within the study area. However, each intersection has been assessed in terms of safety, and appropriate intersection treatments proposed to mitigate any potential safety risks that may arise due to increased turn volumes. This assessment has been conducted according to DTMR's RPDM, chapter 13.

As a conservative approach, the assessment of intersection treatment types is based on existing peak hour traffic volumes and construction traffic occurring at the same time.

14.2.7 Accident analysis

A high level desktop accident analysis was carried out for key roads and intersections within the study area to identify existing traffic safety issues. The following crash data was provided by DTMR:

- Fatal crashes to 31 May 2013 and hospitalisation crashes to 28 February 2013
- Medical treatment, minor injury and property damage crashes to 31 December 2010.

The full set of crash data was not available for 2011 to 2013, instead accident data for five years between 2006 and 2010 were used for the purpose of the assessment.

14.2.8 General assumptions

Transport of hazardous/explosive materials (such as fuel) during construction and operational phase is detailed in Volume 1 Chapter 18 Hazard, risk, health and safety.

14.3 Existing environment

A detailed description of the existing environment is provided in Volume 2 Appendix K Transport.

14.3.1 Road transport network

Key State-controlled roads and local roads

Within the study area, the classification of roads can be used as an indication of each road's existing functional role. Roads of state or regional significance fall under the jurisdiction of DTMR and are considered SCRs. SCRs have four administrative classifications as follows:

- National highway
- State strategic road
- Regional road
- District road.

Local roads fall under the jurisdiction of the relevant local councils and play a functional role in the movement of traffic at a local level.

The SCRs and local roads that will be utilised by construction and operation traffic to access the final rail corridor, camp sites and ancillary infrastructure have been identified and are summarised in Table 14-4.

Table 14-4 Key SCR and local roads

Road name	Extent
State-controlled roads	
Bruce Highway	The main north-south coastal road connecting Brisbane in the south to Cairns in the north. The Bruce Highway is of national importance and extends approximately 1,700 km.
Bowen Developmental Road	Intersects with the Bruce Highway in Bowen and culminates at an intersection with Gregory Developmental Road.
Gregory Developmental Road	Runs in an approximate north-south direction, linking Charters Towers in the north to Clermont in the south. Terminates at an intersection with Peak Downs Highway. Gregory Developmental Road is a State strategic road.
Suttor Developmental Road	Connects Mount Coolon in the west to Nebo in the east, and terminates at Collinsville Elphinstone Road. Suttor Developmental Road is of regional importance.
Key local roads	
Glenore Road	A no-through road that intersects with the Bruce Highway at its northern extent
Stratford Road	A no-through road that intersects with the Suttor Developmental Road at its north eastern extent

Road name	Extent
Strathalbyn Road	A no-through road that intersects with the Bowen Developmental Road and proceeds in a north-west direction.
Strathmore Road	Intersects with the Bowen Developmental Road in Collinsville and proceeds in a westerly direction, eventually changing to Mount Wyatt Road.

Road/rail crossings

The NGBR Project will require the construction of crossings where the final rail corridor intersects with public roads, stock routes, road reserves and occupational (private) trails. A list of roads that will be crossed by the NGBR Project is provided in Table 14-5 and Table 14-6.

Table 14-5 Public road, stock route and road reserve crossings

Crossing	Chainage	Treatment proposed	Property owner
Abbot Point Road	-5.25 km	Road Under Rail	Privately owned by NQBP passing through MIDQ property.
Abbot Point Road	-6.70 km	Road under rail	Privately owned by NQBP passing through MIDQ property.
Abbot Point Road	6.11 km	At-grade	Privately owned by NQBP passing through MIDQ property.
Bruce Highway	12.27 km	Road under rail	DTMR SCR passing through MIDQ property.
Glenore Road	34.05 km	At-grade	WRC road passing through Salisbury Plains property.
Road / stock crossing (gazetted stock route U398BOWN05)	57.34 km	At-grade	DNRM have governance over the easements which form part of the National Stock Route Network. WRC road passing through Eton Vale property.
Strathalbyn Road	61.58 km	At-grade	WRC road passing through Eton Vale property.
Stock crossing (identified gazetted stock route)	62.77 km	At-grade	DNRM have governance over the easements which form part of the National Stock Route Network. This stock route passes adjacent to Eton Vale and Glen Alpine properties.
Road / stock crossing (identified gazetted stock route)	79.55 km	At-grade	DNRM have governance over the easements which form part of the National Stock Route Network. WRC road passing adjacent to Tabletop and Bakara properties.
Road reserve (not constructed)	83.70 km	Close	WRC road passing through Bakara property.

Crossing	Chainage	Treatment proposed	Property owner
Strathmore Road / stock crossing (gazetted stock route U321BOWN01)	97.89 km	At-grade	DNRM have governance over the easements which form part of the National Stock Route Network. WRC road passing through Strathmore property.
Road reserve (not constructed)	117.11 km	Close	WRC road passing through Birralelee property.
Road crossing (minor road)	120.46 km	At-grade	WRC road passing through Birralelee property.
Stock crossing (gazetted stock route U409BOWN02)	133.34 km	At-grade	DNRM have governance over the easements which form part of the National Stock Route Network.
Road reserve (not constructed)	139.27 km	Close	WRC road passing through Havilah property.
Road crossing (minor road)	153.92 km	At-grade	WRC road passing through Fig Tree property.
Bowen Developmental Road	173.20 km	Road over rail	DTMR State-controlled road passing through Cerito property. A road diversion is proposed to maintain or improve horizontal geometry and to mitigate any resultant skew angle on the proposed bridge structure.
Cerito Road (Minor Road)	177.82 km	Close	WRC road passing through Cerito property.
Cerito Road (Minor Road)	180.25 km	At-grade	WRC road passing through Cerito property.
Stock crossing (gazetted stock route U403BOWN02)	186.37 km	At-grade	DNRM has governance over the easements which form part of the National Stock Route Network
Road reserve (not constructed)	205.84 km	Close	WRC road passing through Terang property.
Suttor Developmental Road	231.27 km	At-grade	DTMR State-controlled road passing adjacent to Geneva and Chesterfield properties. A road diversion is proposed to maintain or improve horizontal geometry and to mitigate any resultant skew angle on the proposed bridge structure.
Kilcummin Diamond Downs Road	244.68 km	At-grade	WRC road passing through Glen Avon property.

Crossing	Chainage	Treatment proposed	Property owner
Stratford Road	262.95 km	At-grade	IRC road passing through Stratford property.
Stock crossing (gazetted stock route U402BOWN01)	269.63 km	At-grade	DNRM has governance over the easements which form part of the National Stock Route Network.
Gregory Developmental Road	303.79 km	Road over rail	DTMR SCR passing through Disney property.

Table 14-6 Occupational (private farm) trails

No	Chainage	Treatment proposed	Lot plan	Property name
1	10.85 km	Underpass	1RP705785	Unnamed
2	18.55 km	At-grade	3HR1686	Unnamed
3	20.59 km	Underpass	24RP805036	Salisbury Plains
4	26.69 km	At-grade		
5	36.53 km	At-grade	4SB687	Nevada
6	37.73 km	At-grade		
7	42.42 km	Underpass		
8	43.63 km	Underpass	SB279	Thurso
9	48.58 km	At-grade	3SB514	White Kangaroo
10	52.65 km	Underpass		
11	58.80 km	Underpass	13SP232519	Eton Vale
12	67.32 km	At-grade	5047PH370	Glen Alpine
13	72.09 km	At-grade		
14	83.55 km	Underpass	86DK154	Bakara
15	84.84 km	At-grade		
16	91.35 km	Underpass	3SP132678	Strathmore
17	105.70 km	At-grade		
18	109.56 km	At-grade	9DK17	Myuna
19	114.48 km	At-grade		
20	115.25 km	At-grade	618PH2106	Birrlee
21	119.50 km	Underpass		
22	125.41 km	At-grade		
23	126.83 km	At-grade		


No	Chainage	Treatment proposed	Lot plan	Property name
24	131.75 km	Underpass		
25	140.35 km	At-grade	62SP195387	Havilah
26	142.07 km	At-grade		
27	151.90 km	Underpass	4SP171921	Fig Tree
28	157.05 km	Underpass		
29	169.90 km	Underpass	1510SP171920	Cerito
30	184.35 km	Underpass		
31	186.60 km	Underpass		
32	187.95 km	At-grade	667PH1321	Mount Lookout Holdings
33	193.45 km	At-grade		
34	200.27 km	Underpass		
35	211.65 km	At-grade	1DK244	Terang
36	215.58 km	At-grade		
37	219.54 km	At-grade		
38	222.50 km	At-grade		
39	224.95 km	At-grade		
40	229.40 km	At-grade	1943SP221555	Verbena
41	230.24 km	At-grade		
42	232.15 km	At-grade	1DK150	Chesterfield
43	234.95 km	At-grade	3DC91	Cantaur Park
44	241.95 km	At-grade		
45	250.05 km	At-grade	3821PH1304	Stratford
46	253.98 km	At-grade		
47	266.62 km	At-grade		
48	273.0 km	At-grade		
49	274.05 km	At-grade	10BL49	Avon Downs
50	283.37 km	At-grade		
51	289.08 km	At-grade	4SP116046	Disney
52	295.51 km	Underpass		
53	298.97 km	At-grade		
54	302.92 km	At-grade		

Key intersections and road sections

Key intersections (new and existing) that will facilitate access to the NGBR Project final rail corridor, construction camp sites and other ancillary infrastructure are described in Table 14-7. The locations of these key intersections are shown in Figure 14-1.

Table 14-7 Summary of key intersections

ID	Key intersection	Approximate chainage (km)	Extent and condition	Historical accident data (2006 to 2010)
A	Bruce Highway/New Access Road	14	Proposed two-way, two-lane, sealed road to access Construction Camp 1 and Concrete Batch Plant 1.	Two collisions
B	Glenore Road/New Access Road	34	Proposed unsealed, two-way, two-lane road to access ancillary infrastructure.	No collisions
C	Strathalbyn Road/New Access Road	62	Proposed two-way, two-lane, unsealed road to access Construction Camp 2 and Concrete Batch Plant 2.	No collisions
D	Bowen Developmental Road/New Access Road	120	Proposed two-way, two-lane, sealed road to access Construction Camp 3 and Concrete Batch Plant 3.	No collisions Single accident 3.4 km to south of intersection
E	Bowen Developmental Road/New Access Road	170	Proposed two-way, two-lane, sealed road to access Construction Camp 4, construction yard, Concrete Batch Plant 4 and bridge laydown area.	No collisions Single accident 2.2 km southwest of intersection
F	Suttor Developmental Road/Stratford Road	230	Existing two-way, two-lane, unsealed road will provide access to bridge laydown area	One hit object collision
G	Stratford Road/New Access Road	262	Proposed two-way, two-lane road, unsealed intersection to access Construction Camp 5 and Concrete Batch Plant 5.	No collisions
H	Gregory Developmental Road/New Access Road	305	Proposed two-way, two-lane road, sealed intersection to access ancillary infrastructure.	No collisions




LEGEND

- Population Centres
- Major Port
- Key Intersections
- Highway
- Main Road
- Carmichael Project (Rail)
- Existing/Other Rail Network
- Watercourses (Major)
- North Galilee Basin Rail 1000m Corridor
- North Galilee Basin Rail 100m Corridor

Based on or contains data provided by the State of QLD (DNRM) (2013). In consideration of the State permitting use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, reliability, completeness, currency or suitability) and accepts no liability (including without limitation, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for marketing or be used in breach of the privacy laws.

1:1,100,000 Paper Size A4
0 10 20 40
Kilometres
Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 55



adani

Adani Mining Pty Ltd
North Galilee Basin Rail Project

Job Number 41-26457
Revision B
Date 29 Aug 2013

Key intersections

Figure 14-1

G:\41\26457\06 GIS\Maps\MXD\1000_Transport\41_26457_1004_rev_c.mxd

Level 9, 145 Ann Street Brisbane QLD 4000 Australia T 61 7 3316 3000 F 61 7 3316 3333 E bnemal@ghd.com W www.ghd.com

© 2013. Whilst every care has been taken to prepare this map, GHD, GA, DNRM, Adani make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.
Data source: GA: Populated Places, Railway, Watercourse 2007; Adani: NGBR Corridor 13/05/2013 NGBR Corridor 06/06/2013, Carmichael Rail Project/2013, Chainage/2013; DNRM: Roads/2010; GHD: Study Intersections/2013. Created by:MS

Traffic volumes and capacity of key roads

A LOS approach was used to determine the existing performance of key roads within the study area (refer Section 14.2.5). Table 14-8 provides the AADT and subsequent LOS on all the selected key roads. It should be noted that peak AADT percentages indicating peak hour traffic volumes were not available and therefore 13 per cent of AADT volumes was selected as the peak hour volume in accordance with the Austroads Guide to Traffic Engineering Practice Part 2 recommended range.

Table 14-8 Existing traffic volumes and LOS (2012)

Road name (location)	2012 AADT (Light vehicles)	2012 AADT (Heavy vehicles)	Total (Vehicles /day)	LOS (2012)
Bruce Highway (near chainage 14 km) ¹	2,987	605	3,592	B
Glenore Road (near chainage 34 km) ²	26	3	29	A
Strathalbyn Road (near chainage 62 km) ¹	1,101	115	1,216	A
Bowen Developmental Road (near chainage 120 km) ³	1,234	152	1,386	A
Bowen Developmental Road (near chainage 170 km) ³	286	49	335 ⁴	A
Suttor Developmental Road (near chainage 230 km) ¹	26	3	29	A
Stratford Road (near chainage 262 km) ¹	26	3	29	A
Gregory Developmental Road (near chainage 305 km) ³	586	124	710	A

Note:

1. No data available at location, closest AADT selected
2. No AADT is provided, therefore based on the road location and AADT of a similar road type has been used
3. No data available at location, closest and maximum AADT selected
4. Substantial decrease in traffic along this section of Bowen Developmental Road could be because this station is located further away from town or more built-up areas

All the key roads in Table 14-8 are operating at an existing LOS A with the exception of the Bruce Highway (near chainage 14 km), which is operating at LOS B. The existing LOS at all the selected key roads indicates free and uninterrupted travelling conditions.

Heavy vehicle network

The percentage of heavy vehicles on key roads within the study area is provided in Table 14-9. The heavy vehicle data was based on 2012 AADT counts sourced from DTMR. For any road with multiple count sites, the highest percentage of heavy vehicle information (nearest the study area) was used for a conservative assessment. A map of the DTMR heavy vehicle network is provided in Figure 14-2.

Table 14-9 Percentage heavy vehicles on key roads

Road name (location)	Heavy vehicles
Bruce Highway (near chainage 14 km) ¹	16.8%
Glenore Road (near chainage 34 km) ²	10.3%
Strathalbyn Road (near chainage 62 km) ¹	9.4%
Bowen Developmental Road (near chainage 120 km) ³	10.9%
Bowen Developmental Road (near chainage 170 km) ³	14.6%
Suttor Developmental Road (near chainage 230 km) ¹	10.3%
Stratford Road (near chainage 262 km) ¹	10.3%
Gregory Developmental Road (near chainage 305 km) ³	17.4%

Note:


1. No data available at location, closest AADT selected

2. No AADT is provided, therefore based on the road location and AADT of a similar road type has been used

3. No data available at location, closest and maximum AADT selected

A review of the DTMR heavy vehicle route network shows that:

- Bruce Highway near NGBR final rail corridor is an approved route for B-Double vehicles. This will provide access for B-Double vehicles to Construction Camp 1 and other ancillary infrastructures in the vicinity of this camp
- Bowen Developmental Road between Bowen and Collinsville is an approved route for Type 1 (11 axle and 36.5 metres long) vehicles. This will provide direct access for Type 1 vehicles from the Port of Abbot Point to Construction Camp 3 and other ancillary infrastructure in the vicinity of the Construction Camp 3.
- Bowen Developmental Road between Collinsville, Mount Coolon and Belyando is also an approved route for Type 1 and Type 2 (16 axle and 53.5 metres long) vehicles. This will provide direct access for Type 1 vehicles from the Port of Abbot Point to Construction Camp 4 and associated ancillary infrastructure between Newlands rail system and Mount Coolon
- Suttor Developmental Road between Mount Coolon and Eaglefield is also an approved route for Types 1 and 2 vehicles. This route will be used by Type 1 and Type 2 vehicles to access the bridge and track laydown areas and other ancillary infrastructures in the vicinity
- Gregory Developmental Road between Belyando and Clermont is also an approved route for Type 1 and 2 vehicles. This route will be used by Type 1 and Type 2 vehicles to access the track construction depot and other ancillary infrastructures in the vicinity.



LEGEND

- Town
- Major Port
- Major Road
- Minor Road
- Watercourse
- Heavy Vehicle Road
- Major Highway System (Approved for Higher Mass Limits)
- Additional Roads Approved for Higher Mass Limits
- Existing/Other Rail Network
- Carmichael Project (Rail)
- Carmichael Project (Mine)
- North Galilee Basin Rail

Based on or contains data provided by the State of QLD (DNRM) (2013). In consideration of the State permitting use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, reliability, completeness, currency or suitability) and accepts no liability (including without limitation, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for marketing or be used in breach of the privacy laws.

1:2,500,000 (at A4)
0 20 40 60 80 100
Kilometres
Map Projection: Universal Transverse Mercator
Horizontal Datum: Geocentric Datum of Australia (GDA)
Grid: Map Grid of Australia 1994, Zone 55



adani

Adani Mining Pty Ltd
North Galilee Basin Rail Project

Job Number 41-26457
Revision B
Date 29 Aug 2013

Heavy vehicle transport network

Figure 14-2

G:\41\26457\06 GIS\Maps\MXD\1000_Transport\41_26457_1003_rev_b.mxd

Level 9, 145 Ann St Brisbane QLD 4000 T +61 7 3316 3000 F +61 7 3316 3333 E bnemail@ghd.com W www.ghd.com

© 2013. While GHD Pty Ltd has taken care to ensure the accuracy of this product, GHD Pty Ltd, DME and DNRM make no representations or warranties about its accuracy, completeness or suitability for any particular purpose. GHD Pty Ltd, DME and DNRM cannot accept liability of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred as a result of the product being inaccurate, incomplete or unsuitable in any way and for any reason.
Data Sources: GHD: Ports (2010); G.A: Gazetted Names (2008); Airports/Ports: DNRM: State Roads (2008); DME:EPC1690 (2010), EPC1080 (2011); Adani: Alignment Opt9 Rev3 (2012), NGBR Rail Option 6 Rev 2 (06/06/2013), Carmichael Project Rail (2013). Created by: AJ

Existing public transport network

There is a lack of public and private bus services within the study area. Services operating within the vicinity of the study area include:

- A school bus between Bowen and Collinsville State School (Bowen Transit)
- A school bus between Mount Coolon and Collinsville State School (Bowen Transit)
- Greyhound intercity coaches, servicing Mackay, Proserpine and Bowen via the Bruce Highway.

Active transport network

Active transport networks include footpaths, on-street facilities such as bikeways, bike lanes and shared bicycle facilities. There is currently no pedestrian or cyclist infrastructure along key roads within the study area due to the rural setting, long distances from surrounding communities, the high speed environment of the road network and the low pedestrian and cyclist volumes.

14.3.2 Rail transport network**Freight network**

The existing freight rail network within Central Queensland is shown in Figure 14-3 and includes the following freight line services:

- Blair Athol Branch Railway
- Central Line
- Collinsville-Newlands Branch Railway
- Curragh Branch Railway
- Finch Hatton Branch Railway
- Goonyella Branch Railway
- Great Northern Line
- Gregory Branch
- Kinrola Branch Railway
- Laleham Branch Railway
- North Coast Line
- Northern Missing Link
- Norwich Park Branch Railway
- Springsure Branch Railway
- Wotonga-Blair Athol Branch Railway
- Yaraka Branch Railway.

The NGBR Project final rail corridor is situated to the west of the Newlands rail network primarily interacting with this rail service (via proposed grade-separated crossing) in the northern section of the final rail corridor in the vicinity of Abbot Point.

All the existing freight rail networks in the region are narrow gauged track with 26.5 tonnes axle loads.

Other proposed rail transport infrastructure in the vicinity of the NGBR Project includes:


- GVK Hancock Coal Infrastructure Pty Ltd (GVK-Hancock) is developing the Alpha Coal Railway between its Alpha Coal and Kevin's Corner projects in the Galilee Basin near Alpha, Central Queensland. Technical design has been completed, and State and commonwealth approvals are advanced, however no funding is currently allocated. Aurizon and GVK-Hancock have signed a non-binding term sheet to jointly progress the development of rail and port infrastructure to unlock Galilee Basin coal reserves including GVK Hancock's Alpha, Kevin's Corner and Alpha West coal mines and a process to support the next phase of coal growth in the Bowen Basin.
- Waratah Coal Pty Ltd's Galilee Coal Project which includes a new underground coal mine and associated infrastructure located 30 km north of Alpha in the Galilee Basin as well as a standard gauge rail link, from the mine to the boundary of the Abbot Point State Development Area. State approval was received from the Coordinator-General on 9 August 2013.
- The Central Queensland Integrated Rail Project is proposed by Aurizon and would incorporate a 180 km rail corridor from the Galilee Basin to the existing Newlands system, upgrades and deviation to the Newlands system. Aurizon is preparing an EIS for the Central Queensland Integrated Rail Project. It is noted that there is limited publically available information available for this project.

Adani has previously considered co-utilising a consolidated corridor with GVK Hancock Coal Infrastructure, Waratah Coal and Aurizon. However, with the railway's 60 mtpa capacity already fully allocated, uncertain development timeframes and a route that traverses large areas of floodplain, the potential for co-use of the railway is limited. Further discussion relating to the NGBR Project's relationship to other proposed infrastructure is provided in Volume 1 Chapter 1 Introduction.


Passenger rail network

The existing passenger rail network within Central Queensland is shown in Figure 14-4. The only passenger rail network to be intersected by the NGBR Project final rail corridor (via proposed grade-separated crossing) is the North Coast Line in the northern extent of the study area. There are three services currently operating in the vicinity of the NGBR Project study area:

- Brisbane to Cairns – Queensland Rail's Sunlander and Tilt Train passenger services links Brisbane to Cairns. Two Tilt Train services and two Sunlander services operate per week (each way).
- Brisbane to Longreach – Queensland Rail's Spirit of the Outback passenger service links Brisbane and Longreach. Two train services operate per week (each way).
- Mt Isa to Townsville – Queensland Rail's The Inlander passenger service links Mt Isa and Townsville. One train service operates per week (each way).



Based on or contains data provided by the State of QLD (DNRM) (2013). In consideration of the State permitting use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, reliability, completeness, currency or suitability) and accepts no liability (including without limitation, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for marketing or be used in breach of the privacy laws.



adani

Adani Mining Pty Ltd
North Galilee Basin Rail Project

Job Number 41-26457
Revision B
Date 29 Aug 2013

Freight rail transport network

Figure 14-3

G:\41\26457\06 GIS\Maps\MXD\1000_Transport\41_26457_1007_rev_b.mxd

Level 9, 145 Ann St Brisbane QLD 4000 T +61 7 3316 3000 F +61 7 3316 3333 E bnemail@ghd.com W www.ghd.com

© 2013. While GHD Pty Ltd has taken care to ensure the accuracy of this product, GHD Pty Ltd, DME and DNRM make no representations or warranties about its accuracy, completeness or suitability for any particular purpose. GHD Pty Ltd, DME and DNRM cannot accept liability of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred as a result of the product being inaccurate, incomplete or unsuitable in any way and for any reason.
Data Sources: GHD: Ports (2010); G.A: Gazetted Names (2008) - Airports/Ports; DNRM: State Roads (2008); DME: EPC1690 (2010), EPC1080 (2011); Adani: Alignment Opt9 Rev3 (2012), NGBR Rail Option 6 Rev 2 (06/06/2013), Carmichael Project Rail (2013). Created by: BW, JVC.

14.3.3 Air transport facilities


International and regional airports could potentially serve the fly-in fly-out (FIFO) workforce for the NGBR Project. Currently there are six airports located within the vicinity of the NGBR Project. The nearest international airport is Townsville International Airport. Townsville International Airport is the largest and only international airport in the Central Queensland region, providing connections from capital cities with direct flights servicing Brisbane, Melbourne and Sydney to outlying Central and North Queensland. The airport is situated approximately five kilometres to the north of Townsville city centre. Townsville International Airport processes over 1.6 million passengers annually. The airport has two runways, of which the longest is 2,438 m. Townsville International Airport has four aerobridges (one international and three domestic) for aircraft up to the size of Boeing 767 and three ground level tarmac departure / arrival gates for regional flights at the northern end of the terminal. Passenger airlines operating from Townsville International Airport include Qantas, Virgin Australia, Jetstar, Skytrans and American Airlines.

A number of mining charter flights also currently operate from Townsville International Airport to Cannington Mine, Century Mine, Phosphate Hill Mine, Mount Isa, Osbourne Mine, Mount Dore, Selwyn Mine and Emerald. The airlines which provide these chartered flights include Alliance Airlines and Brindabella Airlines.

The regional airports include:

- Proserpine/Whitsunday Coast Airport - Whitsunday Regional Council is the operator. Proserpine Airport is a domestic airport located approximately 10 km south of Proserpine. It has two asphalt surface runways, of which the longest is 2,073 m. Jetstar and Virgin Australia currently operate daily flights between Proserpine and Brisbane.
- Mackay Airport - Mackay Airport Pty Ltd is the operator. Mackay Airport is a domestic airport that operates flights to Brisbane, Sydney, Melbourne, Gladstone, Rockhampton, Townsville and Cairns. Airlines operating from Mackay Airport include Jetstar, Pel-Air (cargo), Qantas, Tiger Airways and Virgin Australia. Mackay Airport has two asphalt surfaced runways, of which the longest is 1,981 m. This places a limitation on the type of aircraft it can handle.
- Moranbah Airport - BHP Billiton Mitsubishi Alliance is the operator. Moranbah Airport is located off Goonyella Road, approximately six kilometres south of Moranbah. The airport has one runway which is 1,524 m long. Works at the airport (completed mid-2011) included resurfacing the airport runway, improving safety and enabling the airport to be used by larger capacity Q400 aircraft. The airlines currently operating from Moranbah Airport include QantasLink and Skytrans, with flights operating between Moranbah and Brisbane, Cairns, Townsville and Sunshine Coast.
- Clermont Airport - Isaac Regional Council is the operator of this airport. Clermont Airport has two runways, of which the longest is 1,311 m. It is situated just off the Peak Downs Highway near Clermont. Clermont Airport is operated by the IRC and caters to FIFO workforces of nearby mines.
- Emerald Airport – Central Highlands Regional Council are the operator. Emerald Airport is a regional airport located approximately six kilometres from the town of Emerald. It has two runways, of which the longest is 1,900 m. The airport is serviced by two commercial airlines, Qantaslink and Virgin, which fly in and out of Emerald with over 60 services per week.

The locations of air transport facilities are provided in Figure 14-5. The closest airports to the NGBR Project are Proserpine/Whitsunday Coast Airport and Moranbah Airports.



LEGEND

- Town
- Major Road
- Minor Road
- Existing/Other Rail Network
- Watercourse
- ✈ Airport International
- ✈ Airport Regional
- ✈ Local Temporary Airstrips
- Carmichael Project (Rail)
- Project (Mine)
- North Galilee Basin Rail

Based on or contains data provided by the State of QLD (DNRM) (2013). In consideration of the State permitting use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, reliability, completeness, currency or suitability) and accepts no liability (including without limitation, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for marketing or be used in breach of the privacy laws.

1:2,500,000 (at A4)
0 20 40 60 80 100
Kilometres
Map Projection: Universal Transverse Mercator
Horizontal Datum: Geocentric Datum of Australia (GDA)
Grid: Map Grid of Australia 1994, Zone 55



Adani Mining Pty Ltd
North Galilee Basin Rail Project

Job Number 41-26457
Revision B
Date 29 Aug 2013

Air transport facilities

Figure14-5

G:\41\26457\06 GIS\Maps\MXD\1000_Transport\41_26457_1002_rev_b.mxd

Level 9, 145 Ann St Brisbane QLD 4000 T +61 7 3316 3000 F +61 7 3316 3333 E bnemail@ghd.com W www.ghd.com

© 2013. While GHD Pty Ltd has taken care to ensure the accuracy of this product, GHD Pty Ltd, GA, DME and DERM make no representations or warranties about its accuracy, completeness or suitability for any particular purpose. GHD Pty Ltd, GA, DME and DERM cannot accept liability of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred as a result of the product being inaccurate, incomplete or unsuitable in any way and for any reason.

Data Sources: GHD: Ports (2010); GA: Gazetted Names (2008) - Airports/Ports; DMIR: State Roads (2008); DME:EPC1690 (2010), EPC1080 (2011); Adani: Alignment Opt9 Rev3 (2012), NGBR Rail Option 6 Rev 2 (06/06/2013), Carmichael Project Rail (2013). Created by: AJ

14.3.4 Sea transport facilities

The existing bulk ports within the vicinity of the NGBR Project include:

- Port of Townsville
- Port of Mackay
- Port of Hay Point including Dalrymple Bay Coal Terminal and Hay Point Coal Terminal
- Port of Abbot Point
- Dudgeon Point Coal Terminal.

All of these ports are controlled by North Queensland Bulk Ports Corporation (NQBPP) with the exception of the Port of Townsville, which is operated by the Port of Townsville Limited. The Ports of Townsville and Abbot Point would provide facilities suitable for the import of construction materials, components and pre-assembled modules for construction of the NGBR Project.

The locations of the existing sea port infrastructure within the vicinity of the NGBR Project are provided in Figure 14-6.

Port of Townsville

The Port of Townsville comprises nine berths catering for the import and export of a number of commodities, including:

- Fuel, oil and liquid petroleum gas
- Minerals, nickel ore, lead ingots, copper and zinc concentrates
- Containers
- Frozen beef and live cattle
- Cement
- Sugar and molasses
- Sulphuric acid and fertiliser
- Scrap metal, timber and general cargo
- Cruise ships.

Commodities are supplied to the port via both rail and road. The Port of Townsville provides facilities suitable for the import of construction materials, components and pre-assembled modules for construction of the NGBR Project.

An expansion to develop six new berths and reclamation of approximately 100 ha is currently being investigated.

Port of Mackay

The Port of Mackay is located within Mackay harbour and is Queensland's fourth busiest multi-commodity port in terms of cargo throughput. The port is operated by NQBPP. The port comprises four berths catering for the import and export of a number of commodities, including:

- Sugar and sugar products, such as molasses
- Grain
- Sulphuric acid and fertilisers

- Petroleum and ethanol
- Vehicles and machinery.

Port of Hay Point

Hay Point is situated about 40 kilometres south of Mackay. The Port of Hay Point is one of the largest coal export ports in the world. It comprises two coal export terminals, Dalrymple Bay Coal Terminal and Hay Point Coal Terminal.

Dalrymple Bay Coal Terminal is leased from the State Government by Dalrymple Bay Coal Terminal Management Pty Ltd and Hay Point Coal Terminal is owned by BHP Billiton Mitsubishi Alliance and operated by Hay Point Services. Together these coal terminals service the mines in the Bowen Basin in central Queensland. The mines are linked to the port terminals through an integrated rail-port network.

Both terminals have purpose-built, rail in-loading facilities, onshore stockpile yards and offshore wharves. The offshore wharves are serviced by conveyor systems, supported on jetties, which run out to sea and allow loading in deep water.

Plans are progressing for the proposed Dudgeon Point Coal Terminals Project. This expansion at the Port of Hay Point involves two new coal terminals in the port, with an estimated capacity of up to 180 mtpa. The two terminals will be constructed in stages over a 20-year period to meet industry demand. The first stage of development is expected to be a single terminal with a capacity of 30 mtpa.


Dudgeon Point Coal Terminals Project (DPPM) and Adani Mining Pty Ltd (Adani Group) are the preferred proponents for the development of new coal export infrastructure at Dudgeon Point.

Port of Abbot Point and associated coal export terminals

The Port of Abbot Point is operated by NQBP. The Port of Abbot Point is located approximately 25 km north of Bowen and is Australia's most northerly coal port. The port comprises a single coal export terminal, Abbot Point Coal Terminal 1, which is owned (under a 99 year lease) by Adani Abbot Point Terminal Pty Ltd, a subsidiary of the Adani Group, and operated by Abbot Point Bulkcoal Pty Ltd which is a subsidiary of Xstrata.

Abbot Point Coal Terminal 1 comprises a rail in-loading facility, coal handling and stockpile areas, and a dual trestle jetty and conveyors connected to two berths and ship-loaders, located 2.75 km offshore, with a capacity of 50 million tonnes per annum (mtpa). Coal is supplied to the port via the Newlands rail system. Other terminals currently being proposed for development at the Port of Abbot Point include:

- Terminal 0 – proposed for development by Adani with a 70 mtpa capacity
- Terminal 2 – proposed for development by BHP Billiton with a 60 mtpa capacity
- Terminal 3 – proposed for development by GVK-Hancock with a 60 mtpa capacity.



LEGEND

- Town
- ⚓ Major Port
- Minor Road
- Existing/Other Rail Network
- Major Road
- Carmichael Project (Rail)
- Carmichael Project (Mine)
- North Galilee Basin Rail
- Watercourse

Based on or contains data provided by the State of QLD (DNRM) (2013). In consideration of the State permitting use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, reliability, completeness, currency or suitability) and accepts no liability (including without limitation, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for marketing or be used in breach of the privacy laws.

1:2,500,000 (at A4)
0 20 40 60 80 100
Kilometres
Map Projection: Universal Transverse Mercator
Horizontal Datum: Geocentric Datum of Australia (GDA)
Grid: Map Grid of Australia 1994, Zone 55



adani

Adani Mining Pty Ltd
North Galilee Basin Rail Project

Sea transport facilities

Job Number 41-26457
Revision B
Date 29 Aug 2013

Figure 14-6

G:\4126457\06 GIS\Maps\MXD\1000_Transport\41_26457_1001_rev_b.mxd

Level 9, 145 Ann St Brisbane QLD 4000 T +61 7 3316 3000 F +61 7 3316 3333 E bnemail@ghd.com W www.ghd.com

© 2013. While GHD Pty Ltd has taken care to ensure the accuracy of this product, GHD Pty Ltd, GA, DME and DNRM make no representations or warranties about its accuracy, completeness or suitability for any particular purpose. GHD Pty Ltd, GA, DME and DNRM cannot accept liability of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred as a result of the product being inaccurate, incomplete or unsuitable in any way and for any reason.

Data Source: GHD: Ports (2010); GA: Gazetteed Names (2008); Airports/Ports: DNRM: State Roads (2008); DME:EPC1690 (2010); EPC1080 (2011); Adani: Alignment Op9 Rev3 (2012), NGBR Rail Option 6 Rev 2 (06/06/2013), Carmichael Project Rail (2013). Created by: AJ

14.3.5 Proposed transport infrastructure

The Queensland Transport and Roads Investment Program 2013-14 to 2016-17 (QTRIP) details the program of road works DTMR plan to deliver throughout Queensland over a four year period. Projects which have been identified in the immediate vicinity of the NGBR Project are summarised in Table 14-10.

Table 14-10 QTRIP program of works (2013-14 to 2016-17)

Road name	Proposed works	Indicative total cost	Cost and timing
Bruce Highway	Overtaking lanes (Sarina-Cairns)	\$78,000	Approved 2013-14
Bruce Highway	Rest areas (Sarina-Cairns)	\$337,000	Approved 2013-14
Bruce Highway	Safety initiatives	\$259,000	Approved 2013-14
Bruce Highway (Bowen-Ayr)	Improve intersection with Bowen Developmental Road	\$3,720,000	Estimated expenditure June 2013 \$120,000. Approved 2013-14 \$1,000,000. Indicative 2014-15 \$2,600,000
Bruce Highway (Bowen-Ayr)	Improve intersection with Lower Don Road	\$1,504,000	Estimated expenditure June 2013 \$104,000. Approved 2013-14 \$200,000. Indicative 2014-15 \$1,200,000
Bruce Highway (Bowen-Ayr)	Construct overtaking lanes south of Homestead Road	\$4,898,000	Estimated expenditure June 2013 \$601,000. Approved 2013-14 \$4,297,000
Bruce Highway (Bowen-Ayr)	Construct overtaking lanes at Rossiter Hill South	\$5,300,000	Estimated expenditure June 2013 \$807,000. Approved 2013-14 \$4,493,000
Bruce Highway (Bowen-Ayr)	Install, upgrade and replace roadside delineation	\$300,000	Estimated expenditure June 2013 \$100,000. Approved 2013-14 \$200,000
Bruce Highway (Bowen-Ayr)	Rehabilitate pavement	\$2,363,000	Estimated expenditure June 2013 \$314,000. Approved 2013-14 \$2,049,000
Bruce Highway (Bowen to Ayr)	Rehabilitate bridges and culverts	\$43,750,000	Estimated expenditure June 2013 \$22,281,000. Approved 2013-14 \$5,800,000. Indicative 2014-15 \$6,000,000. Indicative 2015-16 to 2016-17 \$9,669,000

Road name	Proposed works	Indicative total cost	Cost and timing
Bowen Developmental Road (Bowen to Collinsville)	Rehabilitate and overlay	\$10,000,000	Approved 2013-14 \$7,000,000. Indicative 2014-15 \$3,000,000
Strathmore Road	Pave and seal	\$700,000	Approved 2015-16 to 2016-17 \$350,000
Strathmore Road	Rehabilitate pavement	\$490,000	Approved 2014-15 to 2015-16 \$245,000
Townsville Port Road	Improve Woolcock Street/Mather Street interchange	\$10,000,000	Estimated expenditure June 2013 \$8,000,000. Approved 2013-14 \$2,000,000
Townsville Port Road	Improve traffic signals at Pilkington Street intersection	\$225,000	Approved 2013-14 \$225,000
Townsville Port Road	Improve traffic signals at Duckworth Street intersection	\$178,000	Approved 2013-14 \$178,000

Source: Queensland Transport and Roads Investment Program 2013-14 to 2016-17 (QTRIP)

Proposed rail infrastructure and proposed port infrastructure are discussed in Section 14.3.2 and Section 14.3.4 respectively.

14.4 Development traffic generation

14.4.1 Construction

Construction of the NGBR Project is anticipated to occur over a period of approximately two years and is scheduled to commence in late 2014. It is estimated that traffic will be generated both within the final rail corridor and on the external road network by the following four types of vehicles during construction:

- Material supply vehicles
- Service vehicles
- Construction workforce via Fly-in/Fly-out (FIFO)
- Construction workforce via Drive-in/Drive-out (DIDO).

Material supply vehicles

The following arrangements, based on the NGBR Concept Design Report (Aarvee Associates 2013), are anticipated for the supply of materials during construction and have been assumed for the purpose of this assessment:

Girders

- Girders will be stockpiled at Townsville Port until a specific bridge site is ready for delivery

- Girders will be transported directly to each bridge site in the month prior to proposed bridge completion
- One 20 m girder will be loaded on each truck from Townsville with no pilot

Culverts

- The likely number of culverts per truck is nine
- Culverts will be delivered directly to each specific drainage structure point or held at bridge sites

Concrete

- The batching rate from each concrete batching plant is anticipated to be 500 m³ per day
- The northern portion of the NGBR Project will have two batching plants, the central portion will have two batching plants and the southern portion will have one batching plant
- A concrete mix of 450 m³ of material (sand, aggregate and cement) will be required to achieve 500 m³ of concrete per day
- Truck capacity of 20 cubic metres or 50 tonne

Sleepers and rail

- Sleepers and rail are expected to be delivered to flash butt welding yards between months 13 and 20 of construction
- Sleepers and rail will be delivered by B-Double trailers (120 sleepers per trailer resulting in 547 trucks per month) and extendible trailers (15 rail sections (each 25 m in length) per trailer resulting in 228 trucks per month).

Ballast

- Approximately 3,330 tonnes are required per kilometre of corridor resulting in approximately 615,000 m³ in total
- A total of 3,250 m³ per day of ballast will be used on work trains
- The ballast is likely to be delivered to the flash butt welding yard and laydown yard between months 13 and 20 of construction and to the siding at chainage 170 km between months 15 and 22
- The capacity of each truck will be 20 cubic metres or 50 tonnes.

Earthworks

- Quantities as per the Mass Haul Calculations dated 12 June 2013, Option 6 Rev 2
- Indicative cut and fill earthwork volumes are provided in Volume 1 Chapter 2 Project description and will be refined during detailed design when more detailed geotechnical field data becomes available
- Fill will be delivered via trucks or scrapers, depending on final source locations
- Rippable material that does not contain oversized rocks will be removed and transported by dozers and scrapers, whereas rocky material will be removed by excavator and transported by dump truck.

Summary of material supply vehicle types

The vehicle types assumed for the purpose of this assessment for the supply of materials during construction are as follows:

- Sleepers – 12.5 m flatbed semitrailer
- Rail (25 m lengths) – 25 m extendable trailers and require vehicle escorts for rails
- Ballast – 19 m trucks for rail line ballast
- Girders – 12.5 m flatbed semitrailer
- Culverts – 12.5 m flatbed semitrailer
- Batching plants – 35 m B-Triple truck
- General fill – Tipping trailer
- Structural fill – 12.5 m flatbed semitrailer
- Capping – B-Double tanker.

While the above material supply vehicle types and configurations have been assumed for the purpose of this assessment, essentially representing a worst-case traffic generation model, there is potential to use other vehicle configurations during construction. These alternate vehicle types and configurations include potential use of B-Double (two trailer) and/or B-Triple (three trailer) road trains to move general and structural fill, capping material, ballast, sleepers and culverts. The capacity of these vehicles could be in the order of approximately 166m³ or 180 – 200 tonnes. The alternate vehicle types and configurations will result in lesser truck trips to move rail materials.

The estimated material supply traffic generation required during the construction phase, based on vehicle types assumed for the assessment, is tabulated in Table 14-12. This table also provides the indicative routes which these vehicles would take to travel between their origin and destinations.

Table 14-11 Estimated monthly material supply truck traffic generation – return trips

	Track				Bridges/ culverts and concrete									Earthworks							
	Sleepers	Rail (25m lengths)	Ballast	Ballast	Girders north	Girders central	Girders south	Culverts north	Culverts central	Culverts south	Batching plants north	Batching plants central	Batching plants south	General fill north	General fill south	Structural fill north	Structural fill central	Structural fill south	Capping north	Capping central	Capping south
From	Townsville	Townsville	Borrow 7	QR quarry-Byerwen	Townsville	Townsville	Townsville	Townsville	Townsville	Townsville	Mackay	Mackay	Mackay	Northern extremities of the Clarke Ranges	Borrow 7	Northern extremities of the Clarke Ranges	Existing QR quarry-Bywewen	Borrow 7	Northern extremities of the Clarke Ranges	Exisiting QR quarry-Byerwen	Borrow 7
To	Construction depot 305 km	Constructi on depot 305 km	Flashbutt welding facility 304 km	Siding-chainage 170 km	Bridge sites x 9 SITES	Bridge sites x 6 SITES	Bridge sites x 5 SITES	Bridge sites x 9 SITES	Bridge sites x 6 SITES	Bridge sites x 5 SITES	Batching plants (1 & 2)	Batching plants (3 & 4)	Batching plant 5	Within corridor through access road	Within corridor through access road	Within corridor through access road	Within corridor through access road	Within corridor through access road	Within corridor through access road	Within corridor through access road	Within corridor through access road
Indicative routes	Via Chaters Towers	Via Chaters Towers	Local access road	Bowen Developm ent Road	Bruce Highway/ Bowen Developmen t Rd	Bruce Highway/ Bowen Developmen t Rd	Gregory Developmen t Rd/ Bowen Developmen t Rd/ Suttor Developmen t Rd	Bruce Highway/ Bowen Developmen t Rd	Bruce Highway/ Bowen Developm ent Rd	Gregory Developmen tal Rd/ Bowen Developmen tal Rd/ Suttor Developmen tal Rd	Bruce Highway/ Bowen Developm ental Rd	Peak Downs Highway/ Suttor Developm ental Rd/ Bowen Developm ental Rd	Peak Downs Highway / Suttor Develop mental Rd/ Stratford Rd	Glenmore Rd	Temp Haul Rd	Glenore Rd	Local Rd/ Temp Haul Rd	Temp Haul Rd	Glenore Rd	Local Rd/ Temp Haul Rd	Temp Haul Rd
Month 6															1,877		2,320	4,335			
Month 7										145	1,350	1,350	675	7,921	1,877	2,153	2,320	4,335			
Month 8							33			145	1,350	1,350	675	7,921	1,877	2,153	2,320	4,335			865
Month 9							33			145	1,350	1,350	675	7,921	1,877	2,153	2,320	4,335		930	865
Month 10							33			145	1,350	1,350	675	7,921	1,877	2,153	2,320	4,335		930	865
Month 11							33				1,350	1,350	675	7,921		2,153	2,320			930	865
Month 12							33		147		1,350	1,350	675	7,921		2,153	2,320			930	865
Month 13	590	252	1,747			20	9		147		1,350	1,350	675	7,921		2,153	2,320			930	865
Month 14	590	252	1,747			24			147		1,350	1,350	675	7,921		2,153	2,320		1,370	930	865
Month 15	590	252	1,747	2,315		25		143			1,350	1,350	675	7,921		2,153	2,320		1,370	930	865
Month 16	590	252	1,747	2,315		22		142			1,350	1,350	675	7,921		2,153	2,320		1,370	930	
Month 17	590	252	1,747	2,315	9	23		142			1,350	1,350	675	7,921		2,153			1,370	930	
Month 18	590	252	1,747	2,315	46						1,350	1,350	675	7,921		2,153			1,370	930	
Month 19	590	252	1,747	2,315	38						1,350	1,350	675	7,921		2,153			1,370	930	
Month 20	590	252	1,747	2,315							1,350	1,350	675	7,921		2,153			1,370	930	
Month 21				2,315										7,921		2,153			1,370		
Month 22				2,315																	

NGBR Project Concept Design Report (Aarvee Associates 2013)

Service supply vehicles

The service supply vehicles that are anticipated to access construction camps during construction include:

- Food transport
- Linen laundering
- Fuel, chemical and explosive supplies
- Waste management contractors
- Maintenance servicemen.

The service supply vehicles are anticipated to be light goods vehicles (with the exception of fuel, chemical and explosive supplies). It has been assumed that there will be 20 service vehicle movements (return trips) per week at each construction camp. At this stage, trips which can be associated with vehicles supplying fuel, chemicals and explosive materials have not been considered in the trip estimation during the construction. However, the number of vehicles supplying these materials is expected to be minimal and would not have any detrimental impact on the road network.

Table 14-12 provides the indicative route that service vehicles would take to travel between origin and destinations.

Table 14-12 Service vehicles indicative route

	Construction Camp at chainage 15 km	Construction Camp at chainage 62 km	Construction Camp at chainage 124 km	Construction Camp at 170 km chainage	Construction Camp at chainage 263 km
From	Bowen	Collinsville	Collinsville	Mount Coolon	Mount Coolon
To	Construction Camp at chainage 15 km	Construction Camp at chainage 62 km	Construction Camp at chainage 124 km	Construction Camp at chainage 170 km	Construction Camp at chainage 263 km
Indicative route	Bruce Highway	Bowen Developmental Road/ Strathalbyn Road	Bowen Developmental Road	Bowen Developmental Road	Suttor Developmental Road/ Stratford Road

Construction workforce via FIFO

A large proportion of the construction workforce will be sourced from areas outside the local area. It is anticipated that approximately 80 per cent of the workforce (1,360 persons at peak) will be flown in from the nearest airports and then transported to the construction camps via buses at the commencement of each work roster. Accommodation for the workers will be provided in purpose built temporary construction camps and each bus will carry 40 passengers. The FIFO workforce has been assumed to fly-in/fly-out from the Proserpine/Whitsunday and Moranbah airports, and transferred to and from the camp sites via buses.

Specialist tradesmen will be sourced from within Queensland and interstate, if necessary, to complete the rail works and skilled labour may be sourced locally from Mackay, Rockhampton and surrounding areas.

The approximate size of construction camps is estimated to be as follows:

- Construction Camp 1 (chainage 15 km) - 300 workers
- Construction Camp 2 (chainage 62 km) - 400 workers
- Construction Camp 3 (chainage 124 km) - 300 workers
- Construction Camp 4 (chainage 170 km) - 400 workers
- Construction Camp 5 (chainage 263 km) - 300 workers.

Table 14-13 provides the indicative route which FIFO vehicles would take to travel between origin and destinations.

Table 14-13 FIFO vehicles indicative route

	Construction Camp at chainage 15 km	Construction Camp at chainage 62 km	Construction Camp at chainage 124 km	Construction Camp at chainage 170 km	Construction Camp at chainage 263 km
From	Proserpine/ Whitsunday Airport	Proserpine/ Whitsunday Airport	Proserpine/ Whitsunday Airport	Moranbah Airport	Moranbah Airport
To	Construction Camp at chainage 15 km	Construction Camp 62 km chainage	Construction Camp at chainage 124 km	Construction Camp at chainage 170 km	Construction Camp at chainage 263 km
Indicative route	Bruce Highway	Bruce Highway/Bowen Development Road/ Strathalbyn Road	Bruce Highway/ Bowen Development Road	Peak Downs Highway/ Suttor Development Road/	Peak Downs Highway/ Gregory Developmental Road

Construction workforce via DIDO

The remaining approximately 20 per cent (approximately 340 persons at peak) of the workforce will be sourced from regional townships in the vicinity of the NGBR Project. The local workforce will make daily trips from regional townships to one of the five temporary construction camp sites. However, due to large travel distances, particularly in the central to southern sections of the final rail corridor, the local workforce may be required to reside in the temporary construction camps when on roster as fatigue management requirements will likely prevent long drives at either end of a shift.

It is anticipated that the typical type of DIDO workforce vehicles will be car or 4WDs with one passenger per vehicle. It was assumed that all the DIDO workforce vehicles will arrive and leave during the morning and afternoon peak hour periods.

Table 14-6 provides the indicative route which DIDO vehicles would take to travel between origin and destinations.

Table 14-14 Estimated DIDO traffic generation (return trips)

	Construction Camp at chainage 15 km	Construction Camp at chainage 62 km	Construction Camp at chainage 124 km	Construction Camp at chainage 170 km	Construction Camp at chainage 263 km
From	Bowen	Collinsville	Collinsville	Mount Coolon	Mount Coolon
To	Construction Camp at chainage 15 km	Construction Camp at chainage 62 km	Construction Camp at chainage 124 km	Construction Camp at chainage 170 km	Construction Camp at chainage 263 km
Indicative route	Bruce Highway	Bowen Developmental Road/ Strathalbyn Road	Bowen Developmental Road	Bowen Developmental Road	Suttor Developmental Road/ Stratford Road

Construction traffic generation

Table 14-15 provides a summary of the estimated total number of construction vehicles that will be required during construction of the NGBR Project. Table 14-15 shows that peak construction traffic is expected to occur in months nine and 10 of the construction schedule.

Table 14-15 Estimated monthly construction vehicles (return trips)

Month	Material supply vehicles	Service vehicles	FIFO workforce vehicles	DIDO workforce vehicles	Total
3	0	40	7	140	187
4	0	260	44	880	1,184
5	0	400	68	1,360	1,828
6	8,532	400	68	1,360	10,360
7	22,126	400	68	1,360	23,954
8	23,024	400	68	1,360	24,852
9	23,954	400	68	1,360	25,782
10	23,954	400	68	1,360	25,782
11	17,597	400	68	1,360	19,425
12	17,744	400	68	1,360	19,572
13	20,329	400	68	1,360	22,157

Month	Material supply vehicles	Service vehicles	FIFO workforce vehicles	DIDO workforce vehicles	Total
14	21,694	400	68	1,360	23,522
15	24,006	400	68	1,360	25,834
16	23,137	400	68	1,360	24,965
17	20,827	400	68	1,360	22,655
18	20,699	400	68	1,360	22,527
19	20,691	400	68	1,360	22,519
20	20,653	320	56	1,120	22,149
21	13,759	320	56	1,120	15,255
22	2,315	280	49	980	3,624
23	0	160	28	560	748
24	0	80	14	280	374

Estimated construction traffic at key roads within study area

Indicative routes for all four construction vehicle types were used to identify the potential construction vehicle demand at the approach roads to the study intersections.

It should be noted that the periods of highest construction traffic volumes on key roads within the study area will vary according to the construction activities and location of works being undertaken during any given month. The estimated monthly construction traffic volumes for each key road within the study area are provided in Table 14-16. The highlighted cells in the table show the critical months (highest estimated construction traffic), which vary at each of the key roads.

Table 14-16 Estimated monthly construction traffic on key roads within the study area (single trips)

Month	A - Bruce Highway	B - Glenore Road	C - Strathalbyn Road	D - Bowen Developmental Road (near chainage 120 km)	E - Bowen Developmental Road (near chainage 170 km)	F - Suttor Developmental Road	G - Stratford Road	H - Gregory Developmental Road
3	0	0	0	166	208	0	0	0
4	166	0	208	664	832	498	498	0
5	664	0	832	664	832	664	664	0
6	664	0	832	664	5,472	664	664	0
7	2,014	20,148	2,182	2,014	6,822	2,072	2,072	58
8	2,014	20,148	2,182	2,014	6,822	2,085	2,085	71
9	2,014	20,148	2,182	2,014	8,682	2,085	2,085	71
10	2,014	20,148	2,182	2,014	8,682	2,085	2,085	71
11	2,014	20,148	2,182	2,014	8,682	2,027	2,027	13
12	2,014	20,148	2,182	2,063	8,731	2,027	2,027	13
13	2,014	20,148	2,182	2,070	8,738	2,018	2,018	1,688
14	2,014	22,888	2,182	2,071	8,739	2,014	2,014	1,684
15	2,046	22,920	2,214	2,022	13,320	2,014	2,014	1,684
16	2,046	22,920	2,214	2,021	13,319	2,014	2,014	1,684
17	2,048	22,922	2,216	2,022	8,680	2,014	2,014	1,684

Month	A - Bruce Highway	B - Glenore Road	C - Strathalbyn Road	D - Bowen Developmental Road (near chainage 120 km)	E - Bowen Developmental Road (near chainage 170 km)	F - Suttor Developmental Road	G - Stratford Road	H - Gregory Developmental Road
18	2,024	22,898	2,192	2,014	8,672	2,014	2,014	1,684
19	2,022	22,896	2,190	2,014	8,672	2,014	2,014	1,684
20	2,014	22,888	2,182	2,014	8,672	1,350	1,350	1,684
21	664	22,888	832	664	5,462	0	0	0
22	664	0	832	498	5,254	0	0	0
23	664	0	832	0	0	0	0	0
24	332	0	416	0	0	0	0	0

Note: Dark cells represent months with highest estimated traffic volume for each approach road

14.4.2 Operation

An overview of the indicative operational workforce traffic generation is provided in Table 14-17. The number of operations staff peaks in 2026 with 369 full-time equivalents.

Table 14-17 Annual operation workforce 2016 to 2026

Operation workforce profile	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026
Tonnage (mtpa)	4	20	30	40	50	60	70	80	90	95	100
Full-time equivalent	66	103	141	173	209	254	315	327	350	361	369

The number of train drivers required during operation will vary with the number of train consists in operation and frequency of train cycles. It is anticipated the majority of the crew will be based out of Bowen, with overnight accommodation provided at the mine camps for changes in shift. A small number of drivers will be based at the yards and provisioning facilities.

The train crew numbers are estimated based on train consist numbers, cycle times and tonnage profile.

14.5 Potential impacts and mitigation measures

Construction and operation of the NGBR Project has the potential to impact the existing transport network that will be utilised for transporting material and personnel, including:

- Key roads
- Key intersections
- Public and active transport
- Proposed infrastructure
- Rail infrastructure
- Air infrastructure
- Port infrastructure.

Construction and operation of the NGBR Project will require direct interaction and potential modification of existing transport infrastructure, including the road network (State and locally controlled), stock route network and rail network. As such, during detailed design and prior to commencement of construction, further consultation will be required with affected infrastructure owners and associated regulatory agencies to inform the following:

Road Impact Assessment (RIA)

Australian Level Crossing Assessment Model (ALCAM)

Pavement Impact Assessment (PIA)

Road Use Management Plan (RUMP).

These reports will identify vulnerable existing infrastructure such as pavements, intersections, bridges and structures and their ability to withstand the expected increase in traffic volumes and types of loads (oversize/indivisible) to be generated during construction of the NGBR Project. Findings from these reports will inform crossing treatment arrangements, impact management practices and the need for Infrastructure Agreements to be made between Adani and the infrastructure owners. Where required, Infrastructure Agreements will include relevant aspects pertaining to construction and operation phases of the NGBR Project, including authorities, responsibilities and commercial aspects for the respective parties.

14.5.1 Construction

The impact of construction traffic was examined on the approach roads of the study intersections. A LOS approach was used to determine the performance of these approach roads. The performance of the road was examined “with” and “without” construction traffic in peak construction year (i.e. 2015) to understand the impacts of the potential construction vehicles on the key roads.

In order to establish the AADT for year 2015, a compound growth rate of three per cent per annum was applied to the 2012 AADT.

The findings of the LOS analysis for the year 2015 are provided in Table 14-18. Table 14-18 indicates that construction traffic will increase the daily traffic volumes on all approach roads, with some anticipated to experience increases of over five per cent (i.e. Strathalbyn Road, Gregory Developmental Road, Stratford Road, Suttor Developmental Road, Bowen Developmental Road and Glenore Road). However, due to the relatively low background traffic volumes on these roads it is expected that these approach roads will operate at LOS C or better, which is acceptable.

Table 14-18 Impact of construction traffic on key roads – 2015

Approach Road	Background traffic (AADT 2012)	Background traffic (AADT 2015)	Construction traffic (2015)	Total traffic (2015)	Per cent increase	LOS-without construction traffic (2015)	LOS-with construction traffic (2015)
Bruce Highway	3592	3925	79	4,005	2%	LOS C	LOS C
Glenore Road	29	32	764	796	2411%	LOS A	LOS A
Strathalbyn Road	1216	1329	89	1,418	7%	LOS A	LOS A
Bowen Developmental Road (near chainage 120 km)	1386	1515	80	1,595	5%	LOS A	LOS A
Bowen Developmental Road (near chainage 170 km)	335	366	459	825	125%	LOS A	LOS A
Suttor Developmental Road	29	32	81	112	255%	LOS A	LOS A
Stratford Road	29	32	81	112	255%	LOS A	LOS A
Gregory Developmental Road	710	776	56	832	7%	LOS A	LOS A

The NGBR Project will require the construction of crossings where the final rail corridor intersects with public roads, stock routes, road reserves and occupational crossings. The method for constructing crossings at public roads will typically require lane closures resulting in minor delays to traffic flows. However, these delays are anticipated to be minimal given the generally low volumes of daily traffic in the study area. To mitigate any potential impacts associated construction of the crossings, site specific Traffic Management Plans will be developed in consultation with the Isaac Regional Council (IRC), Whitsunday Regional Council (WRC) and DTMR, and implemented during construction (refer Table 14-19). Consideration of adequate sight and emergency stopping distances will be included in any traffic management measures. Occupational crossing treatments proposed are subject to ongoing consultation with landholders, as outlined in Volume 2 Appendix B Public consultation.

The construction of grade-separated crossings along the NGBR alignment is unlikely to cause any significant delays to traffic travelling across the existing road network. Any impact on the road network during the construction of the proposed grade-separated crossings will be short-term and managed through the provision of site specific Traffic Management Plans highlighting specific treatments and staged works. Additionally, any impact on the vulnerable bridge structures will also be managed through the provision of site specific Traffic Management Plans. These will be developed in consultation with DTMR, WRC and IRC during detailed design of the NGBR Project. Proposed treatments of crossings are provided in Table 14-5 and Table 14-6.

Public and active transport

The number and frequency of school bus services within the study area are low due to the relatively low population density located along the final rail corridor. No public transport routes have been specifically identified within the study area, although it can be assumed that long-distance buses may travel through the study area and use SCR or local roads in the region. During detailed design, Adani will communicate with bus operators and the public to promote awareness of the impact and management of construction and operation activities. Existing bus services and routes are therefore unlikely to be impacted during construction.

There is currently no existing pedestrian or cyclist infrastructure along any key roads due to the rural setting, long distances from surrounding communities, the high speed environment of the road network and the low pedestrian and cyclist volumes.

Key Intersections

The treatment types at key intersections have been assessed in accordance with the Road Planning and Design Manual, 2nd edition, (RPDM) (DTMR 2013). The assessment of intersection treatment types is based on peak hour vehicular demand to ascertain conservative mitigation measures. The RPDM intersection treatment types that were considered are as follows:


- Basic intersections (Type BA). These intersections are designed to be as compact (and inexpensive) as possible. They are most appropriately used where the volume of turning and traffic is low. The Type BA comprises the following treatments:
 - Basic right turn treatment (BAR) on major road
 - Basic left turn treatment (BAL) on the major and/or minor roads
- Intersections with auxiliary lanes (Type AU). Type AU intersections comprise short lengths of auxiliary lane to improve safety, especially on high speed roads. Such layouts allow traffic to bypass a vehicle waiting to turn right, or a lane for left turning traffic, or both. The AU intersections comprise the following treatments:

- Auxiliary right turn treatment (AUR) on the major road
 - Auxiliary left turn treatment (AUL) on the major road and/or minor roads
- Channelised intersections (Type CH). A channelised intersection is one where conflicting vehicle travel paths are separated by raised, depressed, or painted medians and/or islands. Auxiliary lanes are often used in conjunction with channelisation. The CH intersections comprises the following treatments:
 - Channelised right turn treatment (CHR) on the major road
 - Channelised left turn treatment (CHL) on the major road and/or minor roads.

Bruce Highway / New Access Road

As per the RPDM criteria, CHR short-lane/ AUL short-lane treatments will be undertaken at the Bruce Highway / New Access Road intersection (refer to Figure 14-7). This type of treatment reduces the potential operational and safety risks associated with larger construction vehicles, particularly on an intersection with a SCR (i.e. Bruce Highway).


Figure 14-7 Bruce Highway/New Access Road treatment findings



Glenore Road / New Access Road intersection

As per the RPDM criteria, BAL/BAR treatments will be undertaken at the Glenore Road / New Access Road intersection due to low traffic volumes (refer Figure 14-8). The NGBR Project will provide a priority controlled intersection permitting all the turning movements (except U-turns) at the intersection.


Figure 14-8 Glenore Road/New Access Road treatment findings



Strathalbyn Road / New Access Road intersection

As per the RPDM criteria, BAL/BAR treatments will be undertaken at the Strathalbyn Road / New Access Road intersection due to the low traffic volumes (refer Figure 14-9). The NGBR Project will provide a priority controlled intersection permitting all the turning movements (except U-turns) at the intersection.


Figure 14-9 Strathalbyn Road/New Access Road treatment findings



Bowen Developmental Road / New Access Road intersection (near chainage 120 km)

As per the RPDM criteria, BAL/BAR treatments are proposed at the Bowen Developmental Road / New Access Road intersection due to the low volumes (refer Figure 14-10). However, due to the nature and size of construction vehicles (such as 35 m B-Triple Trucks), a higher standard CHR(S)/AUL(S) treatment will be installed at this intersection. Such a treatment reduces the potential operational and safety risks associated with larger construction vehicles, particularly on an intersection with a SCR (i.e. Bowen Developmental Road). The NGBR Project will provide a priority controlled intersection permitting all turning movements (except U-turns) at the intersection.


Figure 14-10 Bowen Developmental Road/New Access Road treatment findings



Bowen Developmental Road / New Access Road (near chainage 170 km)

As per the RPDM criteria, BAL/BAR treatments are proposed at the Bowen Developmental Road / New Access Road intersection due to the low volumes (refer Figure 14-11). However, due to the nature and size of construction vehicles (such as 35 m B-Triple Trucks), a higher standard CHR(S)/AUL(S) treatment will be installed at this intersection. Such a treatment reduces the potential operational and safety risks associated with larger construction vehicles, particularly on an intersection with a SCR (i.e. Bowen Developmental Road). The NGBR Project will provide a priority controlled intersection permitting all turning movements (except U-turns) at the intersection.


Figure 14-11 Bowen Developmental Road/New Access Road treatment findings



Existing Suttor Developmental Road / Stratford Road intersection

As per the RPDM criteria, BAL/BAR treatments are proposed at this intersection due to the low volumes (refer Figure 14-12). However, due to the nature and size of construction vehicles (such as 35 m B-Triple Trucks), the existing Suttor Developmental Road / Stratford Road intersection will be upgraded to a higher standard CHR(S)/AUL(S). This type of treatment reduces the potential operational and safety risks associated with larger construction vehicles, particularly on an intersection with a SCR (i.e. Suttor Developmental Road). The NGBR Project will provide a priority controlled intersection permitting all turning movements (except U-turns) at the intersection.


Figure 14-12 Suttor Developmental Road/Stratford Road treatment findings



Stratford Road / New Access Road intersection

As per the RPDM criteria, BAL/BAR treatments will be constructed at the Stratford Road / New Access Road intersection due to low traffic volumes (refer Figure 14-13). The NGBR Project will provide a priority controlled intersection permitting all turning movements (except U-turns) at the intersection.


Figure 14-13 Stratford Road/New Access Road treatment findings



Gregory Developmental Road / New Access Road intersection

As per the RPDM criteria, BAL/BAR treatments are proposed at the Gregory Developmental Road / New Access Road intersection due to low traffic volumes (refer Figure 14-14). However, due to the nature and size of construction vehicles (such as 35 m B-Triple Trucks), the NGBR Project will construct a higher standard CHR(S)/AUL(S) treatment at this intersection. Such treatment reduces the potential operational and safety risks associated with larger construction vehicles, particularly on an intersection with a SCR (i.e. Gregory Developmental Road). The NGBR Project will provide a priority controlled intersection permitting all the turning movements (except U-turns) at the intersection.

Figure 14-14 Gregory Developmental Road/New Access Road treatment findings



Proposed road transport infrastructure

Upgrading of the Bruce Highway and improvement works on the Bowen Developmental Road are the only proposed transport infrastructure upgrades that will impact the NGBR Project. These works will improve capacity of roads to facilitate movement of construction materials and workforce to and from the final rail corridor.

Rail transport network

The NGBR Project final rail corridor will run adjacent to the western extent of the Newlands rail network. Interaction of the final rail corridor with the Newlands rail will be primarily confined to the northern portion of the NGBR project in the vicinity of Abbot Point. At chainage 6.75 km, the NGBR Project crosses the existing Abbot Point branch of the Newlands system, part of the Aurizon network. The proposed treatment for this crossing is for the NGBR Project to cross over the Abbot Point branch via a grade-separated crossing.

No passenger rail services operate within the immediate vicinity of the study area. At chainage 12.1 km, the NGBR Project crosses the existing North Coast Line, part of the Queensland Rail network. The proposed treatment for this crossing is for the NGBR Project to cross over the North Coast Line via a grade-separated crossing.

A refinement of the NGBR Project impacts on existing rail infrastructure, at proposed crossing locations, will be undertaken during detailed design, including assessment of current and proposed crossings in accordance with ALCAM. The final treatment at these crossings and any subsequent interfaces with the rail network will be subject to negotiation of Infrastructure Agreements between all relevant parties. These agreements will be developed through the development of the project and will outline infrastructure specific commitments, design and management requirements to be implemented during construction and operation of the NGBR Project.

Air transport facilities

A large proportion of the construction workforce will be sourced from areas outside the local area. It is anticipated that approximately 80 per cent of the workforce (1,360 persons at peak) will be flown in to the nearest airports, Proserpine/Whitsunday and Moranbah airports, and then transported to the construction camps via buses at the commencement of each work roster.

Proserpine/Whitsunday Coast Airport is a domestic airport with two asphalt surface runways. Jetstar and Virgin Australia currently operate daily flights between Proserpine and Brisbane. Moranbah Airport has one runway with QantasLink and Skytrans currently operating between Moranbah and Brisbane, Cairns, Townsville and Sunshine Coast.

Given the existing level of service to these airports from a number of airlines, it is anticipated they have sufficient capacity to cater for the additional NGBR Project FIFO workforce either within existing flights or via additional chartered flights. Furthermore, Mackay Airport, Clermont Airport and Emerald Airport could also service the NGBR Project FIFO workforce should Proserpine/Whitsunday or Moranbah airport not have sufficient capacity.

It is not anticipated that upgrades will be required to any existing airport facilities to cater for the NGBR Project FIFO workforce.

Sea transport facilities

The Ports of Townsville and Abbot Point may provide facilities suitable for the import of construction materials, components and pre-assembled modules for construction of the NGBR Project. Expansion of the Ports of Townsville and Abbot Point are currently being proposed for

development. Such facilities will be beneficial to construction and operation activities associated with the NGBR Project. The NGBR project will directly facilitate additional throughput capacity at the proposed Terminal 0 and existing Terminal 1 coal export terminals at the Port of Abbot Point.

14.5.2 Operation

Operation of the NGBR Project will require a workforce of approximately 369 full-time equivalent staff from 2026 onwards (refer Table 14-17). The majority of this workforce will be accommodated at Bowen or the proposed Carmichael Project (Mine) accommodation camp. The size of the operational workforce required at any time will vary depending on the number of trains in operation. It is expected that 10 train crew members per train will be required. Up to 15 crew members per train may be necessary where trains are few in the early phase of operation. It is anticipated that the majority of the operational workforce will be based out of Bowen, with overnight accommodation provided at the mine camp for changes in shift. A small number of drivers will be based at the rolling stock maintenance yard and provisioning facilities. Cycle times show that crews working loaded trains will work a 12 hour shift, with change-overs occurring at the mine-end and port-end respectively.

Due to the relatively small number of operational workforce, and the current capacity of the existing road network (LOS B and better), operation traffic is anticipated to have a minimal impact on the performance of key roads and key road intersections within the study area.

Maintenance activities throughout operation will include routine rolling stock maintenance and track maintenance as well as major periodic maintenance and emergency response. As the NGBR Project includes a maintenance access road along the length of the final rail corridor, maintenance vehicles are anticipated to have minimal impact on the existing road network during maintenance activities.

14.6 Summary of mitigation measures

A summary of the mitigation and management measures that will be implemented during construction and operation of the NGBR Project are provided in Table 14-19.

Table 14-19 Mitigation measures and timings related to construction and operation activities

Timing	Mitigation measure
Detailed Design	Infrastructure agreements will be developed prior to construction commencing. The agreements will be developed through the development of the project and will outline infrastructure specific management requirements to be implemented during construction and operation n of the NGBR Project
Detailed design	<p>A Road Use Management Plan (RUMP) will be developed in conjunction with the construction contractor and submitted to DTMR/ local Council prior to construction commencing on site. The RUMP will be developed in consultation with DTMR, WRC and IRC to determine the specific requirements of the RUMP and identify appropriate mitigation measures to address the relative increase in traffic levels on affected road sections of the SCR network. A RUMP will be required by DTMR/Council prior to granting a Works Permit to haul material and equipment.</p> <p>The RUMP will identify appropriate protection objectives and associated implementation strategies as well as monitoring, auditing, reporting and corrective actions to be adopted should an undesirable level of impact be experienced. The RUMP will also include requirements by the Queensland Police Service in relation to the safe movement of over-sized/indivisible vehicles.</p> <p>The RUMP will consider the construction and operational phases of the NGBR Project and will serve as the umbrella document for the construction Traffic Management Plan (TMP). To minimise and mitigate the impact of construction traffic on the external road network, the RUMP will include the following management measures:</p> <ul style="list-style-type: none"> • Installation of specific warning signs at local access roads to construction sites to warn existing road users of entering and exiting traffic • Distribution of day warning notices to advise local road users of scheduled construction activities • Advanced notice to road users of lane closures and advice on alternative routes • Installation of appropriate traffic control and warning signs for areas identified where potential safety risk issues exist • Measures for managing transportation of construction materials to maximise vehicle loads and therefore minimise the total number of vehicle movements • Induction of truck and vehicle operators on the requirements of the TMP • Measures for delivery of oversize loads on site • Heavy vehicle routes for construction traffic accessing and exiting construction sites • Site access roads will include adequate sight and emergency stopping distances when positioning roads • Monitoring and tracking of haulage vehicles • Worker transport including mobility impaired workers
Pre-construction	Traffic during construction will be managed through a detailed Traffic Management Plan (TMP). The TMP will address specific items of construction work and issues related to the safe and efficient movement of construction vehicles and haulage of material including the movement

Timing	Mitigation measure
	of site staff. A TMP will be required by DTMR/Council prior to granting a Works Permit to haul material and equipment. Consultation with DTMR, WRC and IRC will also be undertaken in relation to the specific requirements of the TMP.
Pre-construction	A Road Impact Assessment (RIA) will be prepared prior to construction commencing for all key roads and approaches to key intersections in the study area. The RIA will include detailed information on the construction and operation aspects of the NGBR Project (e.g. construction traffic vehicles, quantity of materials to be hauled, haulage routes, quarry locations, program, etc.). The RIA will confirm required road improvements to mitigate the impact of increased construction traffic and locations where a detailed Pavement Impact Assessment (PIA) is required.
Pre-construction	A Detailed Pavement Impact Assessment (PIA) will be prepared and submitted to DTMR/Council prior to construction commencing. The RIA will identify locations on the road network where a detailed pavement impact assessment is required. The detailed PIA will assess the impact of the construction traffic on the life of the affected road pavements and recommend remedial measures. The extent of the remedial measures and compensation will be discussed and agreed with DTMR/Council.
Pre-construction	Construction and operation of the NGBR Project will require direct interaction and potential modification of existing transport infrastructure, including the road network (State and locally controlled), stock route network and rail network. As such, prior to commencement of construction, further investigation and consultation will be undertaken with affected infrastructure owners and associated regulatory agencies regarding final crossing treatment arrangements, impact management practices to be employed and the development and execution of Infrastructure Agreement. This will be confirmed through additional investigations such as a Road Impact Assessment and conducting assessments of current and proposed level crossings in accordance with the ALCAM.
Construction	Temporary traffic management strategies and interface agreements will be developed during detailed design in consultation with DTMR, WRC and IRC for the duration of the construction works and will include consideration of the following: <ul style="list-style-type: none"> • Construction of acceleration / deceleration lanes • Construction of passing lanes to allow construction traffic and through traffic to safely manoeuvre and pass with minimal disruption.
Construction	Coaches used to transport FIFO workers will be compliant with the requirements of the <i>Disability Discrimination Act 1992</i> .
Construction	Adani will communicate with the public and operators of school buses and public transport to promote awareness of the impact and management of construction and operation activities.
Operation	Appropriate controls will be implemented and maintained to access roads during operations to facilitate any ongoing maintenance activities required within the corridor; strategies will include the incorporation of appropriate fencing, gating and signage

14.7 Conclusion

Construction traffic associated with the NGBR Project, including heavy vehicle movements, will create short-term increases in traffic volumes on local and SCRs. However, due to the relatively low existing traffic volumes on these roads, the performance of all key roads is anticipated to operate satisfactorily at LOS C or better. Based on the nominal capacity of the road network, the additional construction traffic resulting from the project can be adequately accommodated at acceptable levels of service.

To minimise the potential impacts of the NGBR Project on key intersections, the following treatment, in accordance with the Road Planning and Design Manual, 2nd edition, will be considered further during detailed design:

- CHR(S)/AUL(S) treatments at the Bruce Highway / New Access Road intersection
- BAL/BAR treatments at the Glenore Road / New Access Road intersection as well as provide a priority controlled intersection permitting all the turning movements (except U-turns)
- BAL/BAR treatments at the Strathalbyn Road / New Access Road intersection due to the low traffic volumes as well as a priority controlled intersection permitting all turning movements (except U-turns)
- CHR(S)/AUL(S) treatments at both of the Bowen Developmental Road / New Access Road intersections (occurring in the proximity of chainage 120 km and 170 km) to accommodate heavy traffic. A priority controlled intersection permitting all turning movements (except U-turns) at the intersection will be included
- The existing Suttor Developmental Road / Stratford Road intersection will be upgraded to a higher standard CHR(S)/AUL(S) to accommodate heavy vehicle traffic. A priority controlled intersection permitting all turning movements (except U-turns) at the intersection will be included.
- BAL/BAR treatments will be constructed at the Stratford Road / New Access Road intersection due to low traffic volumes. A priority controlled intersection permitting all the turning movements (except U-turns) at the intersection will be included.
- CHR(S)/AUL(S) treatments at the Gregory Developmental Road / New Access Road intersection to accommodate heavy traffic. A priority controlled intersection permitting all the turning movements (except U-turns) at the intersection will be included.

Due to the relatively small number of operational workforce, and the currently capacity of the existing road network (LOS A), operation traffic is anticipated to have a minimal impact on the performance of key roads and key road intersections within the study area.