Port of Gladstone Gatcombe and Golding Cutting Channel Duplication Project

Environmental Impact Statement





Appendix L Pavement Impact Assessment

Appendix L

Pavement Impact Assessment

The pavement impact assessment was completed using the spreadsheet published by the Department of Transport and Main Roads (DTMR). Version 28 of the spreadsheet was used being the version available as of March 2018.

The purpose of the pavement impact assessment is to determine the effect that the traffic associated with Project activities has on the road network. The two roads most affected by the Project are Guerassimoff Road (0.5km) and Landing Road (3km). There is short section of private road connecting Landing Road to the site, however this road is unsealed and was therefore excluded from the investigation.

Firstly, the current condition of the road was assessed using various parameters such as the current traffic, predicted growth rates, roughness, etc. Next, the loading due to the Project traffic was calculated by determining the number of truck movements in each direction that are predicted as a result of Project activities. The reduction in pavement life and the maintenance costs as a result of the additional traffic were then calculated.

Below is a list of parameters used in the calculations and how they were calculated/sourced.

| Parameter | Value | Source | | |
|-----------------------------------|-------------------|---|--|--|
| Start of Development Traffic | 2020 | Stated in report | | |
| ESA increase trigger | 5% | Assumed – standard value | | |
| Treasury discount rate | 6% | Default value as specified by TMR | | |
| Inflation | 7% | Default value as specified by TMR | | |
| Development duration | 3 years | As per the report (18 months southern section, 18 months northern section) | | |
| Roughness Increase | 3 counts/ year | Assumed typical value | | |
| AADT 2018 and % Heavy Vehicles | | Obtained by summing weekday 14 hour counts and averaging, applying a factor of 1.1 to obtain 24 hour counts and assumed this was representative (conservative) as an AADT | | |
| Growth adopt | 3% | Assumed | | |
| ESA/HV | 3.2 | The Average ESA value for the Heavy Vehicles (HV), if no value is available a value of 3.2 is used (as recommended by DTMR) | | |
| Existing roughness | | Landing Road – Received counts from Gladstone Regional Council and took the 90th Percentile of the values of the affected section Guerasimoff Road - Assumed 80 | | |
| Terminal roughness | 120 | Assumed typical value | | |
| Seal width | 10m | As stated in the report | | |

The results of the assessment are summarised below.

| | | | Dev. Con | Dev. Contribution (@ the PV Base year) | | | | |
|-------------------|------------------|------|---------------------|--|------------------|-------|----------|--|
| Road name | Reduced Pvt Life | | Rehabilitation (\$) | | Maintenance (\$) | | Total | |
| | То | From | То | From | То | From | (\$) | |
| Guerassimoff Road | 7.8% | 0.6% | \$9,685 | | \$14,979 | \$904 | \$25,568 | |
| Landing Road | 3.3% | 0.3% | | | \$41,677 | \$0 | \$41,677 | |
| Total | | | \$9,685 | \$0 | \$56,656 | \$904 | \$67,245 | |